



MODELS: P33E-NG4 Natural Gas P33E-LP4 Propane

### WARNING:

If the information in these instructions are not followed exactly, a fire or explosion may result causing property damage, personal injury or loss of life.

### FOR YOUR SAFETY

Do not store or use gasoline or other flammable vapors and liquids in the vicinity of this or any other appliance.

Installation and service must be performed by a qualified installer, service agency or the gas supplier.

### FOR YOUR SAFETY

What to do if you smell gas:

- Do not try to light any appliance
- Do not touch any electrical switch: do not use any phone in your building.
- Immediately call your gas supplier from a neighbour's phone. Follow the gas supplier's instructions.
- If you cannot reach your gas supplier, call the fire department.




Installer: Please complete the details on the back cover and leave this manual with the homeowner.

Homeowner: Please keep these instructions for future reference.

### To the New Owner:

### Congratulations!

You are the owner of a state-of-the-art Gas Fireplace by FPI FIREPLACE PRODUCTS INTERNATIONAL LTD. The P33E-4 has been designed to provide you with all the warmth and charm of a wood fireplace at the flick of a switch. The P33E-4 has been approved by Warnock Hersey/Intertek for both safety and efficiency. As it also bears our own mark, it promises to provide you with economy, comfort and security for many trouble free years to follow. Please take a moment now to acquaint yourself with these instructions and the many features of your Regency® Fireplace.







### INFORMATION FOR MOBILE/MANUFACTURED HOMES AFTER FIRST SALE

This Regency® product has been tested and listed by Warnock Hersey/Intertek as a Direct Vent Wall Furnace to the following standards: VENTED GAS FIREPLACE HEATERS ANSI Z21.88-2009/CSA 2.33-2009 and GAS-FIRED APPLIANCES FOR USE AT HIGH ALTITUDES CAN/CGA-2.17-M91.

This Direct Vent System Appliance must be installed in accordance with the manufacturer's installation instructions and the Manufactured Home Construction and Safety Standard, Title 24 CFR, Part 3280, or the current Standard of Fire Safety Criteria for Manufactured Home Installations, Sites, and Communities ANSI/NFPA 501A, and with CAN/CSA Z240-MH Mobile Home Standard in Canada.

This appliance installation must comply with the manufacturer's installation instructions and local codes, if any. In the absence of local codes follow the current National Fuel Gas Code, ANSI Z223.1 and the current National Electrical Code ANSI/NFPA 70 in the U.S.A., and the current CAN/CGA B149 Gas Installation Code and the current Canadian Electrical Code CSA C22.1 in Canada.

The appliance, when installed, must be electrically grounded in accordance with local codes or, in the absence of local codes, with the National Electrical Code, ANSI/NFPA 70, or the Canadian Electrical Code, CSA C22.1.


Ensure that structural members are not cut or weakened during installation.

This Regency® Mobile/Manufactured Home Listed appliance comes factory equipped with a means to secure the unit.

This Regency® Mobile/Manufactured Home listed appliance comes equipped with a dedicated #8 ground lug to which an 18 gauge copper wire from the steel chassis ground must be attached.

This appliance may be installed in an aftermarket permanently located, manufactured (mobile) home, where not prohibited by local codes.

This appliance is only use with the type of gas indicated on the rating plate. This appliance is not convertible for use with other gases, unless a certified kit is used.




### **TABLE OF CONTENTS**

SAFETY LABEL		Flush Louvers	43
		Double Screen Door	43
Cofoty Lobol	5	Optional Bay Door	
Safety Label	5	Optional Bay Trim	
		Bay Louvers	
REQUIREMENTS		Full Screen doors	
		Contemporary Faceplate Installation Part 1	
MA Code - CO Detector	6	Contemporary Faceplate Installation Part 2	
		Contemporary Faceplate Installation Part 3	
INOTAL LATION		Wall Thermostat	
INSTALLATION		Remote Control	
		Wall Switch	
Important Message	7		
Before You Start	7	Wiring Diagrams	
General Safety Information	7	Installing the Optional Fan	53
Requirements			
Checklist		OPERATING INSTRUCTIONS	
Locating Your Fireplace			
Heat Wave Duct System Option		Copy of the Lighting Plate Instructions	54
Unit Dimensions		Operating Instructions	
Unit Dimensions with Contemporary Faceplate		Lighting Procedure	
Clearances w\ Bay or Flush Front		Shutdown Procedure	
•		First Fire	
Clearances w\ Contemporary Faceplate		Aeration Adjustment	
Combustible Mantels		Aeration Adjustment	55
Mantel Leg Clearances w\ Flush or Bay Glass			
Mantel Leg Clearances w\ Contemporary Faceplate		MAINTENANCE	
Framing and Finishing			
Framing Dimensions w\ Contemporary Faceplate		Maintenance Instructions	56
Framing & Finishing w\ Contemporary Faceplate		General Vent Maintenance	
Unit Assembly Prior to Installation		Gold-Plated Louvers/Trim	
Venting Introduction		Log Replacement	
Exterior Vent Termination Locations		Normal Operating Sounds of Gas Appliances	
Regency® Direct Vent Flex System		Glass Gasket	
Installation Procedures	19	Door Glass	
Rigid Pipe Venting Systems		Removing Valve	
4" x 6-5/8" Rigid Pipe Cross Reference Chart	21	•	
Rigid Pipe Venting Arrangements	23	Installing Valve	50
Vertical Termination with Co-Linear Flex System	29		
Venting Arrangements - Vertical Terminations	30	PARTS LIST	
Unit Installation with Horizontal Termination	31		
Unit Installation with Vertical Termination	32	Main Assembly	59
Gas Line Installation	32	Burner & Log Assembly	
Pilot Adjustment		Flush Front & Louvers	
High Elevation		Contemporary Faceplate	
Gas Pipe Pressure Testing	33	Comoniporary i acopiato	
886 S.I.T. Valve Description			
Conversion from NG to LP		WARRANTY	
Optional Brick Panels			
Log Set Installation		The Warranty: Limited Lifetime	67
Standard Flush Door		·	
Optional Flush Trim			
GT Remote Installation			
GTM Remote Installation			
GTMF Remote Installation	4 I		

### SAFETY LABEL

This is a copy of the label that accompanies each P33E-4 Zero Clearance Direct Vent Gas Fireplace. We have printed a copy of the contents here for your review. The safety label is located on the front inside base of the unit, visible when the bottom louver is open.

**NOTE:** Regency® units are constantly being improved. Check the label on the unit and if there is a difference, the label on the unit is the correct one.



For the State of Massachusetts, installation and repair must be done by a plumber or gasfitter licensed in the Commonwealth of Massachusetts.

For the State of Massachusetts, flexible connectors shall not exceed 36 inches in length.

For the State of Massachusetts, the appliances individual manual shut-off must be a t-handle type valve.

The State of Massachusetts requires the installation of a carbon monoxide alarm in accordance with NFPA 720 and a CO alarm with battery back up in the same room where the gas appliance is installed.

### MA Code - CO Detector

(for the State of Massachusetts only)

- 5.08: Modifications to NFPA-54, Chapter 10
- (2) Revise 10.8.3 by adding the following additional requirements:
- (a) For all side wall horizontally vented gas fueled equipment installed in every dwelling, building or structure used in whole or in part for residential purposes, including those owned or operated by the Commonwealth and where the side wall exhaust vent termination is less than seven (7) feet above finished grade in the area of the venting, including but not limited to decks and porches, the following requirements shall be satisfied:
- 1. INSTALLATION OF CARBON MONOXIDE DETECTORS. At the time of installation of the side wall horizontal vented gas fueled equipment, the installing plumber or gasfitter shall observe that a hard wired carbon monoxide detector with an alarm and battery back-up is installed on the floor level where the gas equipment is to be installed. In addition, the installing plumber or gasfitter shall observe that a battery operated or hard wired carbon monoxide detector with an alarm is installed on each additional level of the dwelling, building or structure served by the side wall horizontal vented gas fueled equipment. It shall be the responsibility of the property owner to secure the services of qualified licensed professionals for the installation of hard wired carbon monoxide detectors
- a. In the event that the side wall horizontally vented gas fueled equipment is installed in a crawl space or an attic, the hard wired carbon monoxide detector with alarm and battery back-up may be installed on the next adjacent floor level.
- b. In the event that the requirements of this subdivision can not be met at the time of completion of installation, the owner shall have a period of thirty (30) days to comply with the above requirements; provided, however, that during said thirty (30) day period, a battery operated carbon monoxide detector with an alarm shall be installed.
- 2. APPROVED CARBON MONOXIDE DETECTORS. Each carbon monoxide detector as required in accordance with the above provisions shall comply with NFPA 720 and be ANSI/UL 2034 listed and IAS certified.
- 3. SIGNAGE. A metal or plastic identification plate shall be permanently mounted to the exterior of the building at a minimum height of eight (8) feet above grade directly in line with the exhaust vent terminal for the horizontally vented gas fueled heating appliance or equipment. The sign shall read, in print size no less than one-half (1/2) inch in size, "GAS VENT DIRECTLY BELOW. KEEP CLEAR OF ALL OBSTRUCTIONS".
- 4. INSPECTION. The state or local gas inspector of the side wall horizontally vented gas fueled equipment shall not approve the installation unless, upon inspection, the inspector observes carbon monoxide detectors and signage installed in accordance with the provisions of 248 CMR 5.08(2)(a)1 through 4.
- (b) EXEMPTIONS: The following equipment is exempt from 248 CMR 5.08(2)(a)1 through 4:
- 1. The equipment listed in Chapter 10 entitled "Equipment Not Required To Be Vented" in the most current edition of NFPA 54 as adopted by the Board; and
- 2. Product Approved side wall horizontally vented gas fueled equipment installed in a room or structure separate from the dwelling, building or structure used in whole or in part for residential purposes.
- (c) MANUFACTURER REQUIREMENTS GAS EQUIPMENT VENTING SYSTEM PROVIDED. When the manufacturer of Product Approved side wall horizontally vented gas equipment provides a venting system design or venting system components with the equipment, the instructions provided by the manufacturer for installation of the equipment and the venting system shall include:
- 1. Detailed instructions for the installation of the venting system design or the venting system components; and
- $2.\ A$  complete parts list for the venting system design or venting system.
- (d) MANUFACTURER REQUIREMENTS GAS EQUIPMENT VENTING SYSTEM NOT PROVIDED. When the manufacturer of a Product Approved side wall horizontally vented gas fueled equipment does not provide the parts for venting the flue gases, but identifies "special venting systems", the following requirements shall be satisfied by the manufacturer:
- 1. The referenced "special venting system" instructions shall be included with the appliance or equipment installation instructions; and
- 2. The "special venting systems" shall be Product Approved by the Board, and the instructions for that system shall include a parts list and detailed installation instructions.
- (e) A copy of all installation instructions for all Product Approved side wall horizontally vented gas fueled equipment, all venting instructions, all parts lists for venting instructions, and/or all venting design instructions shall remain with the appliance or equipment at the completion of the installation.

### **INSTALLATION**

## IMPORTANT MESSAGE SAVE THESE INSTRUCTIONS

The P33E-NG4 or P33E-LP4 Direct Vent Fireplace must be installed in accordance with these instructions. Carefully read all the instructions in this manual first. Consult the "authority having jurisdiction" to determine the need for a permit prior to starting the installation. It is the responsibility of the installer to ensure this fireplace is installed in compliance with manufacturer's instructions and all applicable codes.

### **BEFORE YOU START**

Safe installation and operation of this appliance requires common sense, however, we are required by the Canadian Safety Standards and ANSI Standards to make you aware of the following:

INSTALLATION AND REPAIR SHOULD BE DONE BY AN AUTHORIZED SERVICE PERSON. THE APPLIANCE SHOULD BE INSPECTED BEFORE USE AND AT LEAST ANNUALLY BY A PROFESSIONAL SERVICE PERSON. MORE FREQUENT CLEANING MAY BE REQUIRED DUE TO EXCESSIVE LINT FROM CARPETING, BEDDING MATERIAL, ETC. IT IS IMPERATIVE THAT CONTROL COMPARTMENTS, BURNERS AND CIRCULATING AIR PASSAGEWAYS OF THE APPLIANCE BE KEPT CLEAN.

DUE TO HIGH TEMPERATURES, THE APPLIANCE SHOULD BE LOCATED OUT OF TRAFFIC AND AWAY FROM FURNITURE AND DRAPERIES.

WARNING: FAILURE TO INSTALL THIS APPLIANCE CORRECTLY WILL VOID YOUR WARRANTY AND MAY CAUSE A SERIOUS HOUSE FIRE.

CHILDREN AND ADULTS SHOULD BE ALERTED TO THE HAZARDS OF HIGH SURFACE TEMPERATURES, ESPECIALLY THE FIREPLACE GLASS, AND SHOULD STAY AWAY TO AVOID BURNS OR CLOTHING IGNITION.



YOUNG CHILDREN SHOULD BE CARE-FULLY SUPERVISED WHEN THEY ARE IN THE SAME AREA AS THE APPLI-ANCE. TODDLERS, YOUNG CHILDREN AND OTHERS MAY BE SUSCEPTIBLE TO ACCIDENTAL CONTACT BURNS. A PHYSICAL BARRIERS IS RECOMMENDED IF THERE ARE AT RISK INDIVIDUAL IN THE HOUSE. TO RESTRICT ACCESS TO A FIREPLACE OR STOVE, INSTALL AN ADJUSTABLE SAFETY GATE TO KEEP TODDLERS, YOUNG CHILDREN AND OTHER AT RISK INDIVIDUALS OUT OF THE ROOM AND AWAY FROM HOT SURFACES.

CLOTHING OR OTHER FLAMMABLE MATERIAL SHOULD NOT BE PLACED ON OR NEAR THE APPLIANCE.

### GENERAL SAFETY INFORMATION

- The appliance installation must conform with local codes or, in the absence of local codes, with the current Canadian or National Gas Codes, CAN1-B149 or ANSI Z223.1 Installation Codes.
- 2) The appliance when installed, must be electrically grounded in accordance with local codes, or in the absence of local codes with the current National Electrical Code, ANSI/NFPA70 or CSA C22.1 Canadian Electrical Code.
- See general construction and assembly instructions. The appliance and vent should be enclosed.
- 4) This appliance must be connected to the specified vent and termination cap to the outside of the building envelope. Never vent to another room or inside a building. Make sure that the vent is fitted as per Venting instructions.
- Inspect the venting system annually for blockage and any signs of deterioration.
- Venting terminals shall not be recessed into a wall or siding.

- **7)** Any safety glass removed for servicing must be replaced prior to operating the appliance.
- 8) To prevent injury, do not allow anyone who is unfamiliar with the operation to use the fireplace.
- Wear gloves and safety glasses for protection while doing required maintenance.
- **10)** Be aware of electrical wiring locations in walls and ceilings when cutting holes for termination.
- 11) Under no circumstances should this appliance be modified. Parts that have to be removed for servicing should be replaced prior to operating this appliance.
- 12) Installation and any repairs to this appliance should be done by a qualified service person. A professional service person should be called to inspect this appliance annually. Make it a practice to have all of your gas appliances checked annually.
- 13) Do not slam shut or strike the glass door.
- 14) Under no circumstances should any solid fuels (wood, paper, cardboard, coal, etc.) be used in this appliance.
- 15) The appliance area must be kept clear and free of combustible materials, (gases and other flammable vapours and liquids).

Emissions from burning wood or gas could contain chemicals known to the State of California to cause cancer, birth defects or other reproductive harm.

### MANUFACTURED MOBILE HOME ADDITIONAL REQUIREMENTS

- Ensure that structural members are not cut or weakened during installation.
- Ensure proper grounding using the #8 ground lug provided. Refer to "Wiring Diagram" Section.

### INSTALLATION CHECKLIST

- 1) Locate appliance
  - a) Room location

(Refer to "Locating Your Fireplace" Section)

- b) Clearances to Combustibles (Refer to "Clearances" Section)
- c) Mantle Clearances (Refer to "Combustible Mantels" Section)
- d) Framing & Finishing Requirements (Refer to "Framing & Finishing" Section)
- e) Venting Requirements (Refer to "Venting" Sections)
- 2) Assemble Top Facing Support and Side Nailing Strips (Refer to "Unit Assembly Prior to Installation" Section). NOTE: Must be done before installing unit into fireplace.
- 3) Install vent (Refer to "Venting" Sections)
- 4) Make gas and electrical connections. Test the pilot. Must be as per diagram. (Refer to "Gas Line Installation" and "Pilot Adjustment" Section).

Convert to Propane if desired. (Refer to "Conversion Kit from NG to LPG" Section).

- Install 4-AA batteries into the battery pack. Batteries must be installed to operate the burner switch.
- 6) Install standard and optional features. Refer to the following sections:
  - a. Optional Brick Panels
  - b. Log Set Installation
  - c. Standard Flush Door
  - d. Optional Flush Trim
  - e. Double Screen Door
  - f. Optional Bay Door
  - g. Optional Bay Trim
  - h. Flush Louvers
  - i. Bay Louvers
  - j. Full Screen Doors
  - k. Optional Contemporary Faceplate
  - Optional Wall Thermostat
  - m. Optional Remote Control
  - n. Optional Wall Switch
  - o. Installing the Optional Fan
- 7) Final check.

Before leaving this unit with the customer, the installer must ensure that the appliance is firing correctly and operation fully explained to customer.

#### This includes:

- Clocking the appliance to ensure the correct firing rate (rate noted on label) after burning appliance for 15 minutes.
- If required, adjusting the primary air to ensure that the flame does not carbon. First allow the unit to burn for 15-20 min. to stabilize.

CAUTION: Any alteration to the product that causes sooting or carboning that results in damage is not the responsibility of the manufacturer.


### LOCATING YOUR FIREPLACE

- When selecting a location for your fireplace, ensure that the clearances outlined on this page are met.
- 2) Provide adequate clearances for servicing.
- 3) The appliance must be installed on a flat, solid, continuous surface (e.g. wood, metal, concrete). This may be the floor, or raised up on a platform to enhance its visual impact. If the appliance is going to be installed on carpeting, combustible linoleum tile or other combustible material other than wood flooring, the appliance must be installed on a metal or wood panel extending the full width and depth of the appliance.
- 4) The P33E-4 can be installed in a recessed position or framed out into the room as in A, B, C, D. See Diagram 1 below.
- 5) This appliance is Listed for bedroom installations when used with a Listed Millivolt Thermostat. Some areas may have further requirements, check local codes before installation.

- 6) The P33E-4 Direct Vent Gas Fireplace is approved for alcove installations, which meet the clearances listed on the "Clearances" Section.
- 7) We recommend that you plan your installation on paper using exact measurements for clearances and floor protection before actually installing this appliance. Have a qualified inspector, dealer, or installer review your plans before installation.

Note: For vent terminations see "Exterior Vent Termination Locations" Section.

- A) Flat on Wall
- B) Flat on Wall Corner
- C) Recessed into Wall/Alcove
- D) Corner






### DUCT SYSTEM OPTION Kit #946-556


The **HeatWave** Air Duct Kit increases the effectiveness of your fireplace by dispersing warm air from the fireplace to remote locations in the same room or other rooms in your home.

Up to two kits may be installed on the fireplace. **Please Note:** Only 1 HeatWave kit may be operated at one time. This includes the internal blower option as well.


### **UNIT DIMENSIONS**


# 23"(584mm) 33"(838mm)





### UNIT DIMENSIONS WITH CONTEMPORARY FACEPLATE





### **CLEARANCES WITH BAY OR FLUSH FRONT**

The clearances listed below are Minimum distances unless otherwise stated:

A major cause of chimney related fires is failure to maintain

required clearances (air space) to combustible materials.

It is of the greatest importance that this fireplace and vent system

be installed only in accordance with these instructions.

#### Clearance to Combustibles from:

Back	0"	(0mm)
Side	0"	(0mm)
Floor	0"	(0mm)

NOTE: The minimum floor clearance must be maintained

from the top surface of the carpeting, tile, etc.

Minimum Clearance from Top of Unit to:

Mantel\* min. 7" (177mm)

Ceiling 30" (762mm)

from top of unit.

Side Wall Clearance

Bay or Flush Front 7-1/2" (191mm)

### **Minimum Vent Clearances:**

2-1/2" (64mm) Horizontal Top 1-1/2" (38mm) Horizontal Side

1-1/2" (38mm) Horizontal Bottom


1-1/4" (32mm) Vertical Vent Clearance (Rigid Vent)

1-1/2" (38mm) Vertical Vent Clearance (Flex Vent)

#### **Alcove Clearances:**

Max. Depth	36"	(914mm)
Min. Width	48"	(1219mm)
Min. Height	59"	(1499mm)

<sup>\*</sup> see mantel clearance instructions.



Clearances for Bay or Flush Front

#### Warning

Fire hazard is an extreme risk if these clearances are not adhered to.

### **CLEARANCES WITH CONTEMPORARY FACEPLATE**

### The clearances listed below are Minimum distances unless otherwise stated:

A major cause of chimney related fires is failure to maintain required clearances (air space) to combustible materials. It is of the greatest importance that this fireplace and vent system be installed only in accordance with these instructions.

### **Caution Requirements**


The top, back and sides of the fireplace are defined by standoffs. The metal ends of the standoff may **NOT** be recessed into combustible construction.

# Close to Floor

#### WARNING

Fire hazard is an extreme risk

if these clearances (air space) to combustible materials are not adhered to. It is of greatest importance that this fireplace and vent system be installed only in accordance with these instructions.



\*Note: All measurements are from the top/side of the unit, not optional front.

Clearance:	Dimension	Measured From:
A: *Front Floor Clearance (min.)	1" (25mm)	Underside of Unit
B: *Sidewall	7-1/2" (241mm)	Side of Unit
C: *Ceiling (room and/or alcove)	30" (889mm)	Top of Unit
D: Alcove Width	48" (1219mm)	Sidewall to Sidewall (Minimum)
E: Alcove Depth	36" (914mm)	Front to Back Wall (Maximum)

Flue Clearances to Combustibles					
Horizontal - Top	2-1/2"				
Horizontal - Side	1-1/2"				
Horizontal - Bottom	1-1/2"				
Vertical (Flex Vent)	1-1/2"				
Vertical (Rigid)	1-1/4"				

### **COMBUSTIBLE MANTELS**


Because of the extreme heat this fireplace emits, the mantel clearances are critical. Combustible mantel clearances from top of unit are shown in the diagram below.


Note: A non-combustible mantel may be installed at a lower height if the framing is made of metal studs covered with a non-combustible board.

This drawing is to scale at 1:6 (one inch = 6 inches). Mantel can be installed anywhere in shaded area or higher using the above scale.

Note: Ensure the paint that is used on the mantel and the facing is "heat resistant" or the paint may discolour.


Combustible mantel leg clearances as per diagrams below:






### MANTEL LEG CLEARANCES WITH FLUSH OR BAY GLASS

Combustible mantel leg clearances from side of unit as per diagram:



### MANTEL LEG CLEARANCES WITH CONTEMPORARY FACEPLATE


Combustible mantel leg clearances from side of unit as per diagram:




### FRAMING AND FINISHING

 Determine the total thickness of facing material (e.g. drywall plus ceramic tiles) to allow the finished surface to be flush with the front of the unit. Total facing thickness can vary from 1/2" (13mm) to 1-1/4" (32mm) thick.

Install Side Nailing Strips, and Top Facing Support before unit is slipped into position. See "Unit Assembly Prior to Installation" Section




2) Frame in the enclosure for the unit with framing material.



**NOTE:** If this is an outside corner, the minimum distance between the vent and the outside corner is 6" (15cm) with AstroCap termination cap or 12" (30cm) with Rigid Vent termination cap. (For example Dura-Vent).

**NOTE:** Framing is different when using the faceplate option.


See framing section when using faceplate in this manual.



**NOTE:** If this is an outside corner, the minimum distance between the vent and the outside corner is 6" (15cm) with AstroCap termination cap or 12" (30cm) with Rigid Vent termination cap. (For Example Dura-Vent).

- For exterior walls, insulate the enclosure to the same degree as the rest of the house, apply vapour barrier and drywall, as per local installation codes. (Do not insulate the fireplace itself.)
- 4) The top of the unit must not be closer than 30" (762mm) to the ceiling.
- 5) Combustible material may be brought up to the top and sides of the unit and be covered with ceramic tiles, bricks, rock or other suitable combustible finishing materials.

Note: The unit does not have to be completely enclosed in a chase. The clearance on top of the unit is 0" to the standoffs so combustible building materials can be laid directly on top of the standoffs. You must maintain clearance from the vent to combustible materials for flex or for Rigid Vent (Refer to "Clearances" Section).




6) Use steel studs for framing where the 1-1/2" (38mm) clearance from the vent to combustible material cannot be maintained.

### Heat Wave

The **HeatWave** Duct Kit has different clearance and framing requirements, check the **HeatWave** manual for details.

### FRAMING DIMENSIONS WITH CONTEMPORARY FACEPLATE



Framing Dimensions	Description	P33E-4		
G	Framing Width	33-1/4"(845mm)		
Н	Framing Height *	31-3/4"	(806mm)	
I	Framing Rise from Floor	1" (25m	nm) Min.	
J	Framing Depth Vertical Horizontal	19-1/2" (495mm) <i>Vertical Rise</i> 16-1/2" (419mm) <i>Rigid I</i> 12-3/4" (324mm) <i>Flex</i>		
K	Corner Wall Length	37-1/2" (953mm)		
L	Corner Facing Wall Width	53-1/4" (1353mm)		
М	Framed Chase Ceiling*	36" (914mm) Rigid	32" (812mm) Flex	
N	Vent Centerline Height*	30" (762mm) Rigid	26" (660mm) Flex	
0	Gas Connection Height*	1 1/2" (38mm)		
Р	Gas Connection Inset*	4" (102mm)		
Q	Gas Connection Width*	3" (76mm)		

<sup>\*</sup> Measured from base of unit.


### FRAMING & FINISHING WITH CONTEMPORARY FACEPLATE

op-

 Determine the total thickness of facing material (e.g. drywall, wood plus ceramic tiles) to allow the finished surface to be flush with the front of the unit. Total facing thickness can vary from 1/2" (13mm) to 1-1/4" (32mm) thick.

**NOTE:** Facing material may not protrude beyond unit, otherwise the tional accesories will not be able to be mounted to the unit.

Install Side Nailing Strips, and Top Facing Support before unit is slipped into position. See "Unit Assembly Prior to Installation" Section



2) Frame in the enclosure for the unit with framing material.

Note: When constructing the framed opening, please ensure there is access to install the gas lines when the unit is installed.

3) For exterior walls, insulate the enclosure to the same degree as the rest of the house, apply vapour barrier and drywall, as per local installation codes. (Do not insulate the fireplace itself.)

WARNING: Failure to insulate and add vapor barriers to the inside of the exterior wall will result in operational and performance problems including, but not limited to: excessive condensation on glass doors, poor flame package, carbon, blue flames etc. These are not product related issues.

### Important:

If the Contemporary Faceplate is used on the P33E-NG4/P33E-LP4 Gas Fireplace, the burner orifice (Both NG/LP supplied in this package) must be replaced and an overlay decal (also supplied with kit) must be affixed to the current serial number decal supplied with unit.

**Note:** Also see framing dimensions for this optional front if installed on the P33E-4 unit.

**Note:** Unit must be raised up by 1' to allow for faceplate installation.

Current P33E-4 orifice size: #44 #54 Must replace with: #47 #56

Warning: Fire hazard is an extreme risk if these changes are not adhered to.

4) Combustible material may be brought up to the top and sides of the unit and be covered with wood, drywall, ceramic tiles, bricks, rock or other suitable combustible finishing materials.

Note: The unit does not have to be completely enclosed in a chase. The clearance on top of the unit is 0" to the standoffs so combustible building materials can be laid directly on top of the standoffs. You must maintain clearance from the vent to combustible materials for flex or for Rigid Vent (Refer to "Clearances" Section).

5) Use steel studs for framing where the 1-1/2" (38mm) clearance from the vent to combustible material cannot be maintained.

### Heat Wave

The *HeatWave* Duct Kit has different clearance and framing requirements, check the *HeatWave* manual for details.

### UNIT ASSEMBLY PRIOR TO INSTALLATION

The Top Facing Support, the Side Nailing Strips and the 2 Top Standoffs must be correctly positioned and attached to the top before the unit is put into position.

### **Top Standoff Assembly**

The top standoffs are shipped in a flat position and must be pulled up and bent into the correct shape.

- Remove the standoffs from on top of the firebox by undoing the screws.
- 2) Take each standoff and bend into the correct shape. Bend up at the bend lines until the screw holes in the standoff and the pre-punched screw holes on the firebox top line-up.
- Attach the standoffs securely to the top with 4 screws per standoff.


**Note:** Secure the standoffs to the holes closest to the edge of the firebox top.


### Top Facing Support & Side Nailing Strips


Determine the total thickness of facing material (e.g. drywall plus ceramic tiles) to allow the finished surface to be flush with the front of the unit. Total facing thickness can vary from 1/2" (13mm) to 1-1/4" (32mm) thick.


The Top Facing Support & Side Nailing Strips can be mounted in various positions depending on the thickness of the facing material.

- Mount Top Facing Support using the 3 supplied screws into the three pre-punched screw holes on the top front of the unit. Adjust support to desired facing material depth.
- Mount Side Nailing Strip using the 3 supplied screws into the three pre-punched screw holes at the front sides of the unit. Adjust support to desired facing material thickness.









### VENTING INTRODUCTION

The P33E-4 uses the "balanced flue" technology Co-Axial system. The inner liner vents products of combustion to the outside while the outer liner draws outside combustion air into the combustion chamber thereby eliminating the need to use heated room air for combustion and losing warm room air up the chimney.


There are 5 vent systems approved for use with the P33E-4: the Regency® Direct Vent Flex System for Horizontal Terminations only and the Simpson Dura-Vent Pro, Selkirk Direct-Temp, Amerivent Direct Vent, Metal-Fab Sure Seal, Security Secure Vent and ICC Excel Direct for Horizontal and Vertical Terminations (see following "Venting" Sections for more details).

Note: These flue pipes must not be connected to any other appliance.

The gas appliance and vent system must be vented directly to the outside of the building, and never be attached to a chimney serving a separate solid fuel or gas burning appliance. Each direct vent gas appliance must use it's own separate vent system. Common vent systems are prohibited. (See "Rigid Pipe Venting System" for more details and exceptions).

NOTE: Ensure compliance with the outside vent terminal location before cutting hole as both dimensions must be met.

### **EXTERIOR VENT TERMINATION LOCATIONS**



	Minimum Clearance Requirements	Canada <sup>1</sup>	USA <sup>2</sup>
Α	Clearance above grade, veranda, porch, deck, or balcony	12"(30cm)	12"(30cm)
В	Clearance to window or door that may be opened	12"(30cm)	9" (23cm)
С	Clearance to permanently closed window	*	*
D	Vertical clearance to ventilated soffit located above the terminal within a horizontal distance of 2 feet (61cm) from the center line of the terminal (check with the local code)	18"(46cm)	18"(46cm)
E	Clearance to unventilated soffit	15"(38cm)	15"(38cm)
F	Clearance to outside corner: with <i>AstroCap</i> Termination Cap.	6"(15cm)	6"(15cm)
	Clearance to outside corner: with all other approved Termination Caps.	12"(30cm)	12"(30cm)
G	Clearance to inside corner: with <i>AstroCap</i> Termination Cap	6"(15cm)	6"(15cm)
	Clearance to inside corner: with all other approved Termination Caps.	12"(30cm)	12"(30cm)
н	Clearance to each side of center line extended above meter/regulator assembly	36"(90cm) <sup>a</sup>	*
J	Clearance to service regulator vent outlet	36"(90cm)	*
К	Clearance to non-mechanical air supply inlet to building or the combustion air inlet to any other appliance	12"(30cm)	9" (23cm)
L	Clearance to a mechanical air supply inlet #3' (91cm) above if within 10' (3m) horizontally.	72"(1.8m)	36"(90cm) <sup>b</sup>
М	Clearance above paved sidewalk or a paved driveway located on public property	84"(2.1m) <sup>†</sup>	*
N	Clearance under veranda, porch, deck, or balcony	12"(30cm) <sup>‡</sup>	*

In accordance with current CSA B149.1, Natural Gas and Propane Installation Code

In accordance with the current ANSI Z223.1/NFPA 54, National Fuel Gas Code

<sup>+</sup> A vent shall not terminate directly above a sidewalk or paved driveway which is located between two single family dwellings and serves both dwellings. ‡ Permitted only if veranda, porch, deck, or balcony is fully open on a minimum of two sides beneath the floor.

Clearance in accordance with local installation codes and the requirements of the gas supplier
 3 feet (91cm) within a height of 15 feet (4.5m) above the meter / regulator assembly

b 3 feet (91cm) above - if within 10 feet (3m) horizontally

### **REGENCY® DIRECT VENT FLEX SYSTEM**

### **Horizontal Terminations Only**


This venting system, in combination with the P33E-4 Direct Vent Gas Fireplace, have been tested and listed as a direct vent heater system by Warnock Hersey/Intertek. The location of the termination cap must conform to the requirements in the "Exterior Vent Terminal Locations" Section .

Regency® Direct Vent Flex Termination Kit (Part # 946-513) includes all the parts needed to install the P33E-4 with a maximum run of 2 feet. If installing the P33E with a <u>continuous</u> vent length of more than 2 ft (.6m) to a maximum of 10 ft. (3.0m) use Kit # 946-515 (4 ft) or 946-516 (10 ft) or see "Rigid Pipe Venting Systems" Section for alternate venting arrangements.

- 1) 6-7/8" dia. flexible liner (2 ft. length)
- 2) 4" dia. flexible liner (2 ft. length)
- 3) spring spacers (3)
- 4) thimble (2)
- 5) AstroCap termination cap (1)
- 6) screws (12)
- 7) tube of Mill Pac (1)
- 8) plated screws (8)
- 9) screws #8 x 1-1/2" drill point, stainless steel (4)


### Notes:


- 1) Liner sections should be continuous without any joints or seams.
- Only Flex pipe purchased from Regency<sup>®</sup> may be used for Flex installations.



### MINIMUM RIGID PIPE CENTER-LINE

### <u>MINIMUM</u> FLEX KIT CENTER-LINE





Note: for P33E-NG4 with contemporary faceplate - unit must be raised by 1".




Figure 1

Wherever necessary due to external location of cap, the AstroCap can be replaced with the FPI Riser Vent Termination Cap or the Dura-Vent Snorkel Termination Cap.

### INSTALLATION PROCEDURES

for Regency® Direct Vent System (Flex)

 Locate the unit in the framing, rough in the gas (preferably on the right side of the unit) and the electrical (Junction block is on the left side) on the left. Locate the centerline of the termination and mark wall accordingly. Cut a 10"(254mm) hole in the wall (inside dimension).

Note: Tomaketheinstallationmoreaesthetically pleasing, we recommend framing out a square to mount the terminal to.




Note: A 2-1/2" (64mm) horizontal top and 1-1/2" (38mm) horizontal sides & bottom clearance around the liner must be maintained except that only a 1" (25mm) clearance is needed at the termination end. We recommend framing a 10" (254mm) x 10" (254mm) (inside dimensions) hole to give structural rigidity for mounting the termination.

Note: If installing termination on a <u>siding</u>
<u>covered wall</u>, <u>furring strips</u> must be
used to ensure that the termination is
not recessed into the siding.

- 2) Level the fireplace and fasten it to the framing using nails or screws through the nailing strips.
- 3) Assemble the vent assembly by applying Mill Pac to the 4"(100mm) inner collar of the termination and slipping the 4"(100mm) liner over it at least 1-3/8" (35mm). Fasten with the 3 screws (drilling pilot holes will make this easier). Apply Mill Pac or high temperature silicone to the 6-7/8"(175mm) flex pipe and slip it over the 6-7/8" outer collar of the vent terminal at least 1-3/8"(35mm) and fasten with the 3 screws.
- 4) Separate the 2 halves of the wall thimble and securely fasten the one with the tabs to the outside wall making sure that the tabs are on top and bottom. Fasten the other thimble half to the inside wall. The thimble halves slip inside each other and can be adjusted for 2 x 4 or 2 x 6 walls. The liners must slip over the collars a minimum of 1-3/8".

\*If this is an outside corner, the minimum distance between the vent and the outside corner is 6" (15cm) with *AstroCap* termination cap or 12" (30cm) with Dura-Vent termination cap. See "F" in the diagram in "Exterior Vent Termination Locations" Section.




Minimum and Maximum Vent Clearances

- 5) Slip the assembled liner and termination assembly through the thimble making sure the termination cap faces up (there are markings on the cap that show which way is up). This will position the termination cap with proper down slope for draining water. Fasten the cap to the outer wall with the 4 supplied screws.
- 6) Pull the centre 4"(100mm) liner and outer 6-7/8"(175mm) liner out enough to slip over the flue collars of the fireplace.
- 7) Apply Mill Pac over the fireplace inner collar and slip the 4"(100mm) liner down over it and attach with 3 supplied screws.

- 8) Do the same with the 6-7/8"(175mm) liner.
- 9) Apply a bead of silicone between the thimble and termination and around the outer edge of the terminal at the wall in order to keep the water out.

IMPORTANT: Do not locate termination hood where excessive snow or ice buildup may occur. Be sure to check vent termination area after snow falls, and clear to prevent accidental blockage of venting system. When using snow blowers, make sure snow is not directed towards vent termination area.



### RIGID PIPE VENTING SYSTEMS


### **Horizontal or Vertical Terminations**


The minimum components required for a basic horizontal termination are:


- 1 AstroCap Horizontal Termination Cap
- 1 45° Elbow
- 1 Rigid Pipe Adaptor
- 1 Wall Thimble
- Length of pipe to suit wall thickness (see chart)


For siding other than vinyl furring strips may be used, instead of the vinyl siding standoff, to create a level surface to mount the vent terminal. The Terminal must not be recessed into siding.

If a Vinyl Siding Standoff is required (it must be used with vinyl siding), measure to outside surface of wall without siding and add 2 inches.









Do not combine venting components from different venting systems.

However use of the AstroCap  $^{\rm TM}$  and FPI Riser is acceptable with all systems.

This product has been evaluated by Intertek for using a Rigid Pipe Adaptor in conjunction with Duravent Direct-Vent , Selkirk Direct-Temp, Ameri Vent Direct venting and Security Secure Vent systems. Use of these systems with the Rigid Pipe adaptor is deemed acceptable and does not affect the Warnok Hersey/Intertek listing of components.

When using Rigid Vent other than Simpson Dura-Vent, 3 screws must be used to secure rigid pipe to adaptor.

The FPI AstroCap<sup>™</sup> and FPI Riser Vent terminal are certified for installations using FPI venting systems as well as Simpson Dura-Vent® Direct Vent Pro, American Metal Products Ameri Vent Direct Vent, Security Secure Vent®, Selkirk Direct-Temp. AstroCap<sup>™</sup> is a proprietary trademark of FPI Fireplace Products International Ltd. Dura-Vent® and Direct Vent are registered and/or proprietary trademarks of Simpson Dura-Vent Co. Inc.

4" X 6-5/8" RIGID PIPE CROSS REFERENCE CHART
Components from different Manufacturers may not be mixed. Not All Rigid Pipe components are available directly from FPI.

	ts from different Manufactur	rers may not be mixed.	Not all rigid pipe compone	rits are available directly	irom Regency.	
Description	Simpson Direct Vent Pro®	Selkirk Direct Temp™	American Metal Products® Amerivent Direct	Metal-Fab™ Sure Seal	Security Secure- Vent®	ICC Excel Direct
6" Pipe Length-Galvanized	46DVA-06	4DT-6	N/A	4D6	SV4L6	TC-4DL6
6" Pipe Length-Black	46DVA-06B	4DT-6B	N/A	4D6B	SV4LB6	TC-4DL6B
7" Pipe Length-Galvanized	N/A	N/A	4D7	N/A	N/A	N/A
7" Pipe Length-Black	N/A	N/A	4D7B	N/A	N/A	N/A
9" Pipe Length-Galvanized	46DVA-09	4DT-9	N/A	N/A	N/A	N/A
9" Pipe Length-Black	46DVA-09B	4DT-9B	N/A	N/A	N/A	N/A
12" Pipe Length-Galvanized	46DVA-12	4DT-12	4D12	4D12	SV4L12	TC-4DL1
12" Pipe Length-Black	46DVA-12B	4DT-12B	4D12B	4D12B	SV4LB12	TC-4DL1B
18" Pipe Length-Galvanized	46DVA-18	4DT-18	4D18	4D18	SV4LA	TC-4DL18
18" Pipe Length-Black	46DVA-18B	4DT-18B	4D18B	4D18B	SV4LA	TC-4DL18B
24" Pipe Length-Galvanized	46DVA-24	4DT-24	4D24	4D24	SV4L24	TC-4DL2
24" Pipe Length-Black	46DVA-24B	4DT-24B	4D24B	4D24B	SV4LB24	TC-4DL2B
36" Pipe Length-Galvanized	46DVA-36	4DT-36	4D36	4D36	SV4L36	TC-4DL3
36" Pipe Length-Black	46DVA-36B	4DT-36B	4D36B	4D36B	SV4LB36	TC-4DL3B
48" Pipe Length-Galvanized	46DVA-48	4DT-48	4D48	4D48	SV4L48	TC-4DL4
48" Pipe Length-Black	46DVA-48B	4DT-48B	4D48B	4D48B	SV4LB48	TC-4DL4B
60" Pipe Length-Galvanized	46DVA-60	4DT-60	N/A	N/A	N/A	N/A
60" Pipe Length-Black	46DVA-60B	4DT-60B	N/A	N/A	N/A	N/A
, , , , , , , , , , , , , , , , , , ,						
Adjustable Length 3"-10"-Galvanized	N/A	N/A	N/A	4DAL	N/A	TC-4DLT
Adjustable Length 3"-10"-Black	N/A	N/A	N/A	4DALB	N/A	TC-4DLTB
Adjustable Length 7"-Galvanized	N/A	N/A	4D7A	N/A	N/A	N/A
Adjustable Length 7"-Black	N/A	N/A	4D7AB	N/A	N/A	N/A
Extension Pipe 8-1/2"-Galvanized	46DVA-08A	N/A	N/A	N/A	N/A	N/A
Extension Pipe 8-1/2"-Black	46DVA-08AB	N/A	N/A	N/A	N/A	N/A
Adjustable Length 12"-Galvanized	N/A	N/A	4D12A	N/A	SV4LA12	N/A
Adjustable Length 12"-Black	N/A	N/A	4D12A	N/A	SV4LBA12	N/A
Extension Pipe 16"-Galvanized	46DVA-16A	N/A	N/A	N/A	N/A	N/A
Extension Pipe 16"-Black	46DVA-16AB	N/A	N/A	N/A	N/A	N/A
45° Elbow-Galvanized	46DVA-E45	4DT-EL45	4D45L	I N/A	I N/A	TE-4DE45
45° Elbow-Black	46DVA-E45B	4DT-EL45B	4DT-EL45B	N/A	N/A	TE-4DE45B
45° Elbow Swivel-Galvanized	See 46DVA-E45	N/A	N/A	4D45L	SV4E45	N/A
45° Elbow Swivel-Black	See 46DVA-E45B	N/A	N/A	4D45LB	SV4EB45	N/A
90° Elbow-Galvanized	46DVA-E90	4DT-EL90S	4DT-EL90S	N/A	N/A	TE-4DE90
90° Elbow-Black	46DVA-E90B	4DT-EL90SB	4DT-EL90SB	N/A	SV4EBR90-1	TE-4DE90B
90° Elbow, Swivel-Galvanized	See 46DVA-E90	N/A	N/A	4D90L	SV4E90-1	N/A
90° Elbow, Swivel-Black	See 46DVA-E90B	N/A	N/A	4D90LB	SV4EB90-1	N/A
90° Starter Elbow, Swivel-Galvanized	N/A	N/A	N/A	4D90LB 4D90A	N/A	N/A N/A
Adaptor*	N/A	N/A	N/A	4D90A 4D90L	N/A	N/A
<u> </u>						
Ceiling Support	N/A	4DT-CS	4DFSP	4DSP	SV4SD	TE-4DE45
Cathedral Support Box	46DVA-CS	4DT-CSS	4DRSB	4DRS	SV4CSB	TE-4DE45B
Wall Support/Band	46DVA-WS	4DT-WS/B	4DWS	4DWS	SV4BM	N/A
Offset Support	46DVA-ES (N/A - FPI)	4DT-OS	N/A	N/A	SV4SU	N/A
Wall Thimble-Black	46DVA-WT	4DT-WT	4DWT	4DWT	SV4RSM	TE-4DE90
Vall Thimble Support/Ceiling Support	46DVA-DC	N/A	N/A	N/A	SV4PF	TE-4DE90B
Firestop Spacer	46DVA-FS	4DT-FS	4DFSP	4DFS	SV4BF	N/A
Trim Plate-Black	N/A	4DT-TP	4DFPB	4DCP	SV4LA	N/A

Description	Simpson Direct Vent Pro®	Selki Direct Te		American Metal Products® Amerivent Direct	Metal-Fab™ Sure Seal	Security Secure- Vent®	ICC Excel Direct	
Attic Insulation Shield 12"	46DVA-IS N/A@ FPI	N/A		4DAIS12	N/A	SV4RSA	N/A	
Attic Insulation Shield - Cold Climates 36"	N/A	N/A		4DAIS12	N/A	N/A	TM-4AS	
Basic Horizontal Termination Kit (A)	Disc.	4DT-HKA		4DHTK2	4DHTKA	SV-SHK	N/A	
Horizontal Termination Kit (B)	46DVA-KHA (Changed Components)	4DT-HKB		4DHTK1	4DHTKB	SV-HK	N/A	
Vertical Termination Kit	Disc.	4DT-VKC		4DHTK	4DHTK	SV-FK	N/A	
High Wind Vertical Cap	46DVA-VCH	N/A		N/A	N/A	I N/A	TM-4VT	
High Wind Horizontal Cap	46DVA-HC	N/A		N/A	N/A	N/A	TM-4DHT	
Horizontal Square Termination Cap	See 46DVA-HC	4DT-HHC		4DHC	4DHT	SV4CHC-1	TM-4HT	
Vertical Termination Cap	46DVA-VC	4DT-HVC		4DVC	4DVT	SV4CGV-1	TM-4VT	
Storm Collar	46DVA-08A	4DT-SC		4DSC	4DSC	SV4FC	TM-SC	
Adjustable Flashing 0/12-6/12	46DVA-F6	4DT-ST14		4D12S	4DST14	SV4STC14	TF-4FA	
Adjustable Flashing 6/12-12/12	46DVA-FLA	4DT-ST36		4D36S	4DST36	SV4STC36	TF-4FB	
Vinyl Siding Standoff	46DVA-VSS	4DT-VS		l <sub>N/A</sub>	4DVS	SV4VS	Tm-vss	
Vinyl Siding Shield Plate	N/A	4DT-VSP		N/A	N/A	SV4VS	N/A	
Viriyi Olding Ollield Flate	IV/A	1401-401		19/5	IV/A	100400	N/A	
Snorkel Termination 14"	46DVA-SNKL	N/A		N/A	N/A	N/A	TM-4ST14	
Snorkel Termination 36"	N/A	N/A		N/A	N/A	N/A	TM-4ST36	
	1				1			
Restrictor Disk	N/A	N/A		N/A	N/A	N/A	TM-4DS	
Extended Vertical Termination Cap	N/A	N/A		N/A	N/A	N/A	N/A	
Chimney Conversion Kit A (USA only)	46DVA-KCA	N/A		N/A	N/A	N/A	TM-4CA6	
Chimney Conversion Kit B (USA only)	46DVA-KCB	N/A		N/A	N/A	N/A	TM-4CA7	
Chimney Conversion Kit C (USA only)	46DVA-KCC	N/A		N/A	N/A	N/A	TM-4CA8	
Chimney Conversion Kit Masonry (USA only)	46DVA-KMC	N/A		N/A	N/A	N/A	N/A	
Wall Firestop	46DVA-WFS	N/A		N/A	N/A	N/A	TM-4TR	
Colinear Flex Connectors	46DVA-ADF N/A			N/A	N/A	N/A	N/A	
FPI								
946-506/P Vent Guard (Option	onal) for AstroCap		946-20	5	Vinyl Siding Shiel	Vinyl Siding Shield for Riser Vent Terminal		
510-994 Rigid Pipe Adapto	or (Must use with all rigid piping)		946-20	8/P	Vent Guard (Option	Vent Guard (Optional) for Riser Vent Terminal		
640-530/P Riser Vent Termin				3/P	AstroCap Horizon	AstroCap Horizontal Cap		
946-605 Starter Collar Incr	Starter Collar Increaser 4" x 6-5/8" to 5" x 8"			6	Vinyl Siding Stand	Vinyl Siding Standoff for AstroCap		

Note: When using Metal-Fab Sure Seal Rigid Piping - please note that the Adaptor (4DDA) must be used in conjunction with FPI Rigid Pipe Adaptor (510-994).

Offset Pipe Selection: Use this table to determine offset pipe lengths.							
Pipe Length	4" x 6-5/8	B" Venting		For specific instructions on venting components - visit the			
(L)	Run (X)	Rise (Y)		manufacturers website listed below.			
0" (0mm)	4-7/8" (124mm)	13-7/8" (340mm)		Simpson Direct Vent Pro: www.duravent.com			
6" (152mm)	8" (203mm)	16-1/2" (419mm)		Selkirk Direct-Temp: www.selkirkcorp.com			
9" (229mm)	10-1/8" (257mm)	18-5/8" (473mm)		American Metal Products: www.americanmetalproducts.com			
12" (305mm)	12-1/4" (311mm)	20-3/4" (527mm)		Metal-Fab Sure Seal: www.mtlfab.com			
24" (610mm)	20-5/8" (524mm)	29-1/8" (740mm)		Security Secure Vent: www.securitychimneys.com			
36" (914mm)	29" (737mm)	37-1/2" (953mm)		Industrial Chimney Company: www.icc-rsf.com			
48" (1219mm)	37-7/16" (951mm)	45-15/16" (1167mm)	<b>→</b> x →				

Note: Horizontal runs of vent must be level, or have a 1/4" rise for every 1 foot of run towards the termination.

Never allow the vent to run downward - this could cause high temperatures and may present a possible fire hazard.





Redency Fireplace Products . 6988 Venture St. . Delta. BC . Canada . V4G 1H4 . 604-946-5155 . www.redency-fire.com

### **RIGID PIPE VENTING ARRANGEMENTS**

### Vertical Terminations (Propane & Natural Gas)

The shaded area in the diagram shows all allowable combinations of straight vertical and offset to vertical terminations, using one 90° elbow, with **rigid pipe** vent systems for Propane and Natural Gas.





- Vent must be supported at offsets.
- · Firestops are required at each floor level and whenever passing through a wall.
- Maintain clearances to combustibles.
- When using Contemporary Faceplate, unit must be raised 1".


Note: Must use optional rigid pipe adapter when using rigid vent systems (Part # 510-994).

### **INSTALLATION**

The P33E-4 is approved for a maximum 40 ft. straight vertical, with **rigid pipe** vent systems for Propane and Natural Gas.

The shaded area in the diagram shows all allowable combinations of straight vertical and offset to vertical terminations with **rigid pipe** vent systems for Propane and Natural Gas.  $\underline{\text{Maximum two } 45^{\circ} \text{ elbows allowed.}}$ 

- Vent must be supported at offsets.
- Firestops are required at each floor level and whenever passing through a wall.
- Maintain clearances to combustibles.
- When using Contemporary Faceplate, unit must be raised 1".




### RIGID PIPE VENTING ARRANGEMENTS


# Horizontal Terminations REGENCY® DIRECT VENT SYSTEM (FLEX) (Propane & Natural Gas)

This diagram shows all allowable combinations of vertical runs with horizontal terminations, <u>using one 45° and one 90° elbow</u> (two 45° elbows equal one 90° elbow).


Note: Must use optional rigid pipe adaptor (Part # 510-994) when using rigid pipe vent systems. (Refer "Rigid Pipe Venting Systems" Section)



### <u>Minimum</u> <u>Simpson Dura-Vent Center-Line</u>



### <u>Minimum</u> Flex Kit Center-Line



### Horizontal Venting with Two (2) 90° Elbows

### One 90° elbow = Two 45° elbows.

Option	V	H + H1
A)	1' Min.	3' Max.
B)	2' Min.	4' Max.
C)	3' Min.	5' Max.
D)	4' Min.	6' Max.
E)	5' Min.	7' Max.
F)	6' Min.	8' Max.

With these options, maximum total pipe length is 30 feet with minimum of 6 feet total vertical and maximum 8 feet total horizontal.

Please note minimum 1 foot between 90° elbows is required.


### Horizontal Venting with Three (3) 90° Elbows

One 90° elbow = Two 45° elbows.

Option	Н	٧	H+H1+H2
A)	1' Max.	1' Min.	3' Max.
B)	2' Max.	3' Min.	5' Max.
C)	3' Max.	5' Min.	6' Max.
D)	4' Max.	7' Min.	7' Max.
E)	5' Max.	9' Min.	8' Max.
F)	6' Max.	11' Min.	9' Max.


With these options, maximum total pipe length is 30 feet with minimum of 11 feet total vertical and maximum 9 feet total horizontal.

Please note minimum 1 foot between 90° elbows is required.



### Horizontal Venting with Two (2) 90° Elbows

### One 90° elbow = Two 45° elbows.




Option	Н	V	H+H1
A)	1' Max.	1' Min.	3' Max.
B)	2' Max.	2' Min.	5' Max.
C)	3' Max.	4' Min.	6' Max.
D)	4' Max.	6' Min.	7' Max.
E)	5' Max.	8' Min.	8' Max.

Ф

With these options, maximum total pipe length is 30 feet with minimum of 8 feet total vertical and maximum 8 feet total horizontal.

Please note minimum 1 foot between 90° elbows is required.





### Vertical Venting with Two (2) 90° Elbows One 90° elbow = Two 45° elbows.

8'

10'

Option	V	Н	V+V1	
A)	1' Min.	4' Max.	2' Min.	
B)	2' Min.	5' Max.	3' Min.	
C)	3' Min.	6' Max.	4' Min.	
D)	4' Min.	7' Max.	5' Min.	
E)	5' Min.	8' Max.	6' Min.	

Option

A)

B)

C)

D)

E)

F)

٧

2' Min.

3' Min.

4' Min.

Min.

5'

6' Min.

7' Min. Н

1' Max.

2' Max.

3' Max.

4' Max.

5' Max.

6' Max.

With these options, maximum total pipe length is 30 feet with minimum of 6 feet total vertical and maximum 8 feet total horizontal.

Please note minimum 1 foot between 90° elbows is required.


### Vertical Venting with Two (2) 90° Elbows

One 90° elbow = Two 45° elbows.

Option	H + H1	٧
A)	2' Max.	2' Min.
B)	3' Max.	3' Min.
C)	4' Max.	4' Min.
D)	5' Max.	5' Min.
E)	6' Max.	6' Min.

With these options, maximum total pipe length is 30 feet with minimum of 6 feet total vertical and maximum 6 feet total horizontal.

Please note minimum 1 foot between 90° elbows is required.




### Vertical Venting with Three (3) 90° Elbows

One 90° elbow = Two 45° elbows.


n	Option	Н	V	H + H1	V + V1	With these option
	A)	1' Max.	1' Min.	3' Max.	3' Min.	pipe length is 30
	B)	2' Max.	2' Min.	4' Max.	l	of 11 feet total
	C)	3' Max.	3' Min.'	5' Max.	/ IVIIII.	max. 7 feet tota
	D)			6' Max.	9 IVIIN.	Please note between 90°
	E)	5' Max.	5' Min.	7' Max.	11' Min.	required.

With these options, max. total pipe length is 30 feet with min. of 11 feet total vertical and max. 7 feet total horizontal.

Please note min. 1 foot between 90° elbows is required.



### Vertical Venting with Three (3) 90° Elbows



### One 90° elbow = Two 45° elbows.

Option	V	H + H1	V + V1
A)	2' Min.	3' Max.	4' Min.
B)	3' Min.	4' Max.	6' Min.
C)	4' Min.	5' Max.	7' Min.
D)	5' Min.	6' Max.	8' Min.
E)	6' Min.	7' Max.	9' Min.
F)	7' Min.	8' Max.	10' Min

With these options, max. total pipe length is 30 feet with min. of 10 feet total vertical and max. 8 feet total horizontal.

Please note min. 1 foot between 90° elbows is required.

### VERTICAL TERMINATION WITH CO-LINEAR FLEX SYSTEM

THE APPLIANCE MUST NOT BE CONNECTED TO A CHIMNEY FLUE SERVING A SEPARATE SOLID FUEL BURNING APPLIANCE.

Masonry chimneys may take various contours which the flexible liner will accommodate. However, **keep the flexible liner as straight as possible**, avoid unnecessary bending.

The Air Intake pipe must be attached to the inlet air collar of the termination cap.

This appliance is designed to be attached to two 3" (76mm) co-linear aluminium flex running the full length of the chimney. See the "Venting Arrangements - Vertical Terminations" Section for minimum and maximum heights.


### **Required Parts:**

Part # Description 946-529 Co-linear DV Vertical **Termination Cap** 948-305 3" Flex - 35 ft. 946-563 Co-Axial to Co-Linear Adapter Kit which contains the following: Co-linear Flex Adapter Outer Pipe Inner Pipe Adapter 510-994 Rigid Pipe Adaptor 46DVA-E45 45° Elbow

### **Alternate Approved Caps**


46dva-VC Vertical Termination Cap 46dva-VCH High Wind Cap

46dva-GK 3" Co-linear Adapter with flashing



### **VENTING ARRANGEMENTS - VERTICAL TERMINATIONS**

with Co-linear Flex System for both Residential & Manufactured Homes into Masonry Fireplaces



When using Contemporary Faceplate, unit must be raised 1".

The shaded area in the diagrams show the allowable vertical terminations.


### UNIT INSTALLATION WITH HORIZONTAL TERMINATION

Install the vent system according to the manufacturer's instructions included with the components.

- 1) Set the unit in its desired location. Check to determine if wall studs or roof rafters are in the way when the venting system is attached. If this is the case, you may want to adjust the location of the unit. Rough in the gas preferably on the right side of the unit and the electrical (junction block is on the left side) on the left.
- 2) Direct Vent pipe and fittings are designed with special twist-lock connections to connect the venting system to the appliance flue outlet. A twist-lock appliance adaptor is an available option that must be used in conjunction with the Simpson Dura-Vent Direct Vent system.
- 3) Put a bead of silicone inside the outer section of the adapter and a bead of Fireplace Mate on the inner collar. Slip the adapter over the existing inner and outer flue collar and fasten to the outer collar only with the 3 supplied screws (drilling pilot holes will make this easier). Level the fireplace and fasten it to the framing using nails or screws through the nailing strips.
- Assemble the desired combination of pipe and elbows to the appliance adaptor and twist-lock for a solid connection.

#### Note:

a) Twist-lock procedure: Four indentations, located on the female ends of pipes and fittings, are designed to slide straight onto the male ends of adjacent pipes and fittings, by orienting the four pipe indentations so they match and slide in to the four entry slots on the male ends, Dia. 1. Push the pipe sections completely together, then twist-lock one section clockwise approximately one-quarter turn, until the two sections are fully locked. The female locking lugs will not be visible from the outside, on the Black Pipe or fittings. They may be located by examining the inside of the female ends.



NOTE: For best results and optimum performance with each approved venting system, it is highly recommended to apply "Mill-Pac" sealant (supplied) to every inner pipe connection. Failure to do so may result in drafting or performance issues not covered under warranty. Silicone (red RTV) is optional.

- b) Horizontal runs of vent must be supported every three feet. Wall straps are available for this purpose.
- 5) Mark the wall for a 10" x 10" square hole. The center of the square hole should line up with the centerline of the horizontal pipe. Cut and frame the 10 inch square hole in the exterior wall where the vent will be terminated. If the wall being penetrated is constructed of non-combustible material, i.e. masonry block or concrete, a 7"(178mm) diameter (7-1/2"(191mm) dia. for flex) hole is acceptable.


### Note:

- a) The horizontal run of vent must be level, or have a 1/4 inch rise for every 1 foot of run towards the termination. Never allow the vent to run downward. This could cause high temperatures and may present the possibility of a fire.
- b) The location of the horizontal vent termination on an exterior wall must meet all local and national building codes, and must not be blocked or obstructed. See "Exterior Vent Terminal Locations" Section.


#### c) Snorkel Terminations:

For installations requiring a vertical rise on the exterior of the building, 14-inch and 36-inch tall Snorkel Terminations and the Riser Vent as shown in Dia. 2 & 2a are available. Follow the same installation procedures as used for standard Horizontal Termination. NEVER install the snorkel upside down.

**Below Grade Snorkel Installation** If the Snorkel Termination must be installed below grade, i.e. basement application,




\*As specified in CGA B149 Installation Code. Local codes or regulations may require different clearances.



proper drainage must be provided to prevent water from entering the Snorkel Termination. Refer to Dura-Vent Installation instructions for details. Do not attempt to enclose the Snorkel within the wall, or any other type of enclosure.

6) The arrow on the vent cap should be pointing up. Insure that the 1-1/2" clearances to combustible materials are maintained (Dia. 3). Install the termination cap. AstroCap™ or Dura-Vent Horizontal Termination Cap may be used.

The four wood screws provided should be replaced with appropriate fasteners for stucco, brick, concrete, or other types of sidings.




Note: If installing termination on a siding covered wall, a vinyl siding standoff or furring strips must be used to ensure that the termination is not recessed into the siding.

7) Before connecting the horizontal run of vent pipe to the vent termination, slide the Wall Thimble (Part # 620-926) over the vent pipe.


### **INSTALLATION**


- 8) Slide the appliance and vent assembly towards the wall carefully inserting the vent pipe into the vent cap assembly. It is important that the vent pipe extends into the vent cap sufficient distance so as to result in a minimum pipe overlap of 1-1/4 inches. Secure the connection between the vent pipe and the vent cap 3 sheet metal screws.
- Install wall thimble in the center of the 10" square and attach with wood screws (Diagram 4).




# UNIT INSTALLATION WITH VERTICAL TERMINATION

 Maintain the 1-1/2" clearances (air spaces) to combustibles when passing through ceilings, walls, roofs, enclosures, attic rafter, or other nearby combustible surfaces. Do not pack air spaces with insulation. Check "Venting" Sections






3) A Firestop spacer must be installed in the floor or ceiling of every level. To install the Firestop spacer in a flat ceiling orwall, cut a 10 inch square hole. Frame the hole as shown in Diagram 2 and install the firestop.



4) Assemble the desired lengths of pipe and elbows. Ensure that all pipes and elbow connections are in the fully twist-locked position and sealed.



NOTE: For best results and optimum performance with each approved venting system, it is highly recommended to apply "Mill-Pac" sealant (supplied) to every inner pipe connection. Failure to do so may result in drafting or performance issues not covered under warranty. Silicone (red RTV) is optional.

5) Cut a hole in the roof centered on the small drilled hole placed in the roof in Step 2. The hole should be of sufficient size to meet the minimum requirements for clearance to combustibles of 1-1/2". Slip the flashing under the shingles (shingles should overlap half the flashing) as per Diagram 3.





Diagram 3: The upper half of the flashing is installed under the roofing material and not nailed down until the chimney is installed. This allows for small adjustments.

6) Continue to assemble pipe lengths.

Note: If an offset is necessary in the attic to avoid obstructions, it is important to support the vent pipe every 3 feet, to avoid excessive stress on the elbows, and possible separation. Wall straps are available for this purpose.

Galvanized pipe is desirable above the roofline due to its higher corrosion resistance. Continue to add pipe sections through the flashing until the height of the vent cap meets the minimum height requirements specified in Dia. 4 or local codes. Note that for steep roof pitches, the vertical height must be increased. A poor draft, or down drafting can result from high wind conditions near big trees or adjoining roof lines, in these cases, increasing the vent height may solve the problem.

7) Ensure vent is vertical and secure the base of the flashing to the roof with roofing rails, slide storm collar over the pipe section and seal with a mastic.



Roof Pitch	Minimum Ve	nt Heigh
	Feet	Meters
flat to 7/12	2	0.61
over 7/12 to 8/12	2	0.61
over 8/12 to 9/12	2	0.61
over 9/12 to 10/12	2.5	0.76
over 10/12 to 11/12	3.25	0.99
over 11/12 to 12/12	4	1.22
over 12/12 to 14/12	5	1.52
over 14/12 to 16/12	6	1.83
over 16/12 to 18/12	7	2.13
over 18/12 to 20/12	7.5	2.29
over 20/12 to 21/12	8	2.44

8) Install the vertical termination cap by twistlocking it.

Note: Any closets or storage spaces, which the vent passes through must be enclosed.

### GAS LINE INSTALLATION

The gas line is brought through the right side of the appliance. The gas valve is situated on the right hand side of the unit and the gas inlet is on the right hand side of the valve.

The gas line connection may be made of rigid pipe, copper pipe or an approved flex connector. (If you are using rigid pipe, ensure that the valve can be removed for servicing.) Since some municipalities have additional local codes it is always best to consult with your local authorities and the CAN/CGA B149 installation code.


For USA installations follow local codes and/or the current National Fuel Gas Code, ANSI Z223.1.

When using copper or flex connectors use only approved fittings. Always provide a union so that gas lines can be easily disconnected for servicing. Flare nuts for copper lines and flex connectors are usually considered to meet this requirement.

Important: Always check for gas leaks with a soap and water solution or gas leak detector. Do not use open flame for leak testing.

### **PILOT ADJUSTMENT**

Periodically check the pilot flames. Correct flame pattern has two strong blue flames: 1 flowing around the flame sensor and 1 flowing across the burner (it does not have to be touching the burner).



Note: If you have an incorrect flame pattern, contact your Regency® dealer for further instructions.

Incorrect flame pattern will have small, probably yellow flames, not coming into proper contact with the rear burner or flame sensor.

### HIGH ELEVATION

This unit is approved in Canada for altitude to 4500 ft. (CAN/CGA-2.17-M91). For Natural Gas installations above 4500 ft. follow current CAN/CGA-B149.1.

### P33E-NG4 System Data

### With Flush or Bay Glass:

For 0 to 4500 feet altitude

Burner Inlet Orifice Sizes: #44 Max. Input Rating 20,000 Btu/h Min. Input Rating 14,000 Btu/h

### With Contemporary Faceplate:

For 0 to 4500 feet altitude

Burner Inlet Orifice Sizes #47 Max. Input Rating 17,500 Btu/h Min. Input Rating 9,800 Btu/h

Supply Pressure min.5.0" w.c.

**Manifold Pressure** 

(High) 3.5"+/- 0.2" w.c.

### P33E-LP4 System Data

With Flush or Bay Glass:

For 0 to 4500 feet altitude **Burner Inlet Orifice Sizes:** #54

Max. Input Rating 20,000 Btu/h Min. Input Rating 16,500 Btu/h

With Contemporary Faceplate:

For 0 to 4500 feet altitude **Burner Inlet Orifice Size** #56

Max. Input Rating 15,500 Btu/h 9,000 Btu/h

Supply Pressure min.11.0" w.c.

Manifold Pressure

(**High**) 10"+/- 0.2"w.c.

### GAS PIPE PRESSURE TESTING

The appliance must be isolated from the gas supply piping system by closing its individual manual shutoff valve during any pressure testing of the gas supply piping system at test pressures equal to or less than 1/2 psig. (3.45 kPa). Disconnect piping from valve at pressures over 1/2 psig.


The manifold pressure is controlled by a regulator built into the gas control, and should be checked at the pressure test point.


Note: To properly check gas pressure, both inlet and manifold pressures should be checked using the valve pressure ports on the valve.

- 1) Make sure the switch is in the "OFF" position.
- Loosen the "IN" and/or "OUT" pressure tap(s), turning counterclockwise with a 1/8" wide flat screwdriver.
- Attach manometer to "IN" and/or "OUT" pressure tap(s) using a 5/16" ID hose.
- Light the pilot by turning the switch to "ON" position.
- 5) The pressure check should be carried out with the unit burning and the setting should be within the limits specified on the safety label.
- 6) When finished reading manometer, turn off the gas valve, disconnect the hose and tighten the screw (clockwise) with a 1/8" flat screwdriver. Note: Screw should be snug, but do not over tighten.

### 886 S.I.T. VALVE DESCRIPTION

- Manual high/low adjustment
- 2) Pilot adjustment
- 3) Outlet Pressure Tap
- 4) Inlet Pressure Tap
- 5) Pilot Outlet
- 6) Main Gas Outlet
- 7) Main Gas Inlet





### **CONVERSION FROM NG TO LP**

For P33E-4 Using SIT 886 NOVA Gas Valve

### THIS CONVERSION MUST BE DONE BY A QUALIFIED GAS FITTER IF IN DOUBT DO NOT DO THIS CONVERSION!!

### Each Kit contains one LPG Conversion Kit

LPG Conversion Kit Contains: Qty. Part # Description

-		
1	904-163	Burner Orifice #54
1	918-590	Decal "Converted to LPG"
1	908-528	Red "LPG" label
1	904-529	5/32" Allen Key
1	910-101	LPG Injector (Pilot Orifice)
1	911-009	Hi/Lo Conversion LP
1	918-856	Instruction Sheet

### For the U32SE only:

3) Remove the burner by undoing the 2 screws as shown below.



Burner




Lift up from the back.

### Installation of the LPG Conversion Kit:

- 1) Shut off the gas supply.
- 2)
- a) Remove the louvers, bay door or faceplate if installed.
- b) Remove the logs, embers, and brick panels (if installed).
- 3) Remove the glass door.
  - a) Release the two hooks from the bottom of the glass door.



**b)** Swing the door out 45 degrees from the bottom - then lift up and out.



 After screws have been removed, slide the burner to the left, then lift out carefully.




Remove the base cover by lifting up from the back, then maneuver it out.



Base Cover



Remove burner orifice with a 1/2" wrench and discard. Use another wrench to hold onto the elbow behind the orifice.



Burner Orifice

- 7) Install the new LP burner orifice stamped #54 and tighten.
- 8) Remove the pilot shield by removing the 2 screws as shown below.



### **INSTALLATION**



Pilot Cap

Pull off the pilot cap to expose the pilot orifice.



10) Unscrew the pilot orifice with the supplied allen key and replace it with the LP pilot orifice and re-install the pilot cap and the pilot shield.



- 11) Re-install base cover.
- 12) Re-install the burner.

NOTE: Before re-installing the burner, ensure the LP areation setting is set at 1/2" min. when using glass crystals and 1/8" min. when using ceramic stones.

13) Follow steps 19 - 26 on this page.

### For the P33E unit only:


14) Remove the 2 screws holding the Burner Assembly to the firebox base. Push the Burner Assembly to the left and lift out.



Remove the 2 screws, push Burner Assembly to the left and lift out.



**15)** Undo clip and remove pilot cap to expose pilot orifice.



Pilot Cap

Clip

16) Unscrew the pilot orifice with the Allen key and replace with the LPG pilot orifice in the kit and replace pilot cap.



17) Remove burner orifice with a 1/2" wrench and discard. Use another wrench to hold on to the elbow behind the orifice.



Burner Orifice

18) Reinstall new burner orifice LPG stamped #54 or LPG Orifice #56 for use with Faceplate (orifice supplied with faceplate) and tighten.

#### For both U32SE & P33E-4 units:

19) Remove regulator and discard. Install the Hi/Lo pressure regulator onto the valve with 2 screws as shown below.



- **20)** Attach the label "This unit has been converted to LPG" near or on top of the serial # decal.
- **21)** Replace yellow "NG" label with red "LPG" label.
- 22) Reverse step 3 1
- 23) Check for gas leaks.
- 24) Check inlet and outlet pressures.

### Warning for P33E unit

Must install LPG Orifice #54 for use with Flush, Louver, or Bay Door.


Must install LPG Orifice #56 for use with Faceplate.

### **Installer Notice:**

These instructions must be left with the appliance.


### OPTIONAL BRICK **PANELS**

- 1) Undo the bottom 2 door latches and open and remove glass door. Remove logs.
- 2) Attach the 2 Rear Brick Retaining clips to the rear wall. Loosen the screws in the top and rear wall of the firebox and slide the retaining clips into position (tight against the firebox top) and then tighten the screws.




Note: The logs must not be in the unit.

3) Insert the back brick panel by carefully slipping it between the back wall of the firebox and the rear log bracket.



4) Put the side panels in next. Slide them in from the front and push them flat up against the wall. Be very careful not to scratch them on the firebox hardware.



5) Slide the Top Brick Panel into position and slide the Top Brick Retaining clips so that they hold the Top Brick Panel in place and tighten down the screws.



### LOG SET INSTALLATION

Read the instructions below carefully and refer to the diagrams. If logs are broken do not use the unit until they are replaced. Broken logs can interfere with the pilot operation.

The 3-digit numbers (i.e. 250) are molded into the rear of each log.

Log Kit # 431-930 contains the following pieces:

C) D)	250 254 253 251 252	Rear Log Middle Cross Log Front Left Cross Log Rear Left Log Front Right Cross Log Embers	902-156
G)		Vermiculite	902-179
H)		Rock Wool	902-173
'			
I)		Platinum Embers	946-669
		(supplied with packaged m	nanual)

NOTE: If you will be installing the optional Brick Panels, install the Brick Panels prior to installing the logs.

- 1) Carefully remove the logs from the box and unwrap them. The logs are fragile, handle with care - do not force into position.
- 2) Sprinkle the vermiculite and embers around the firebox base.




Vermiculite Vermiculite Vermiculite

3) Place the Log 250 on the rear log support pins with the flat side to the back.





A) 250




4) Place Log 254 on the front right side of the burner. Push the back of the log against the 2 brackets with the notch on the bottom right side of the log fitting into the right side of the grate.



Bracket Bracket



Position Log 253 across the cutouts in Logs 250 and 254 with the notch on the left side of the log fitting into the 2nd grate




2nd Grate Tab

### **INSTALLATION**



 Place the bottom left front edge of Log <u>251</u> against the left edge of the burner tray and rest the log on the cutout on Log <u>253</u>.



Cutout

 Position Log <u>252</u> across the cutouts in Logs 254 and 253. The notch in the bottom right end fitting against the 5th grate tab.



5th Grate Tab



8) Pull off ember size pieces of rock wool and gently place them on the front of the burner tray in the places shown in the photo below. Do not compress the rock wool, leave it loose.

Separate platinum embers and place them on the front of the burner on and around the rock wool.





Place rock wool in these 2 locations on the burner tray.

9) Test fire to ensure proper light off (make sure flame flows smoothly from one end of burner to the other). If there is any flame hesitation, check that area for any blockage of the burner ports.

## STANDARD FLUSH DOOR

The standard flush door comes with a black frame. To install the frame, simply hook the top door flange onto the top of the unit and swing the door towards the unit, diagram 1. Be careful that the glass gasket does not roll up; there must be a gap between the gasket and the door lip to ensure that the door sits securely on the unit. See Diagram 2.






Flush Door Glass

Gasket:
Correct
Door/Glass/Gasket
Installation.

Diagram 2


Use the hook to pull the spring out until you can put the hook into the slot on the bottom door bracket. Repeat for 2nd spring. See diagram 3.



To remove the flush door, reverse the above steps.

# OPTIONAL FLUSH TRIM

Attach the round magnets to the back of the top trim piece and to the bottom trim piece, then attach trim to the top and bottom of Flush door.



### **GT REMOTE INSTALLATION**

- 1) Shut off the gas supply and disconnect all power to the unit.
- 2) Remove the louvers, bay door or faceplate if installed.
- Disconnect battery pack located on the floor of the unit, as shown below and discard.




4) Remove DFC (digital firebox control box) from the floor of the unit.



5) Disconnect wire harness, ground wire and spark wire from DFC. See attached wiring diagram for details.



- **6)** Identify wires in the GT remote wiring harness. (see wiring diagram.)
- Connect the TPTH and TH wires green to green and white to white as shown below. See attached wiring diagram for details.



8) Plug in receiver DC supply wire - as shown below.



9) Install 4 - AA batteries into the receiver, ensure correct polarity.



10) Plug receiver wires into the back of the receiver and bundle wires with the wire clip as shown below.





Wire Clip

11) Install the heat shield to the receiver with two screws and attach to the floor of the unit with a velcro pad.



Heat Shield

- 12) Reverse steps 5 and 4.
- 13) Match the remote control to the receiver see remote control instructions.
- 14) Reverse steps 2 and 1.
- 15) Check to ensure there are no gas leaks.

### **GTM REMOTE INSTALLATION**

- 1) Shut off the gas supply and disconnect all power to the unit.
- 2) Remove the louvers, bay door or faceplate if installed.
- Disconnect battery pack located on the floor of the unit, as shown below and discard.



4) Remove DFC (digital firebox control box) from the floor of the unit.



5) Disconnect wire harness, ground wire and spark wire from DFC.



DFC

- **6)** Identify wires in the GTM/GTMF remote wiring harness. (see wiring diagram.)
- 7) Connect the TPTH and TH wires green to green and white to white as shown below.



8) Plug in receiver DC supply wire - as shown below.



9) Remove the hi/lo knob if installed by removing 2 screws as shown below.




**10)** Install the stepper motor in the same location the hi/lo knob was removed from - with 2 screws as shown below.



11) Remove the receiver if installed - unplug the motor wire from the back of the receiver - as shown below.




- 12) Reattach wires from step 5.
- 13) Plug the stepper motor into the 'motor wire as shown below.



Motor wire

**14)** To unattach these wires - un-clip from the wires on the stepper motor side as shown below.



Press down this tab


15) Install 4-AA batteries into the receiver.



16) Bundle all wires together and clip with supplied wire clip - as shown below.



17) Install the heat shield to the receiver with two screws and attach to the floor of the unit with a velcro pad - also peel off paper on back side of wire clip and place wires conveniently in appliance.



- 18) Match the remote control to the receiver see remote control instructions.
- 19) Reverse steps 2 and 1.
- 20) Check to ensure there are no gas leaks.

### **GTMF REMOTE INSTALLATION**

- 1) Shut off the gas supply and disconnect all power to the unit.
- 2) Remove the louvers, bay door or faceplate, if installed.
- 3) Disconnect battery pack located on the floor of the unit, as shown below and discard.



- 4) Identify wires in the GTM/GTMF remote wiring harness. (see wiring diagram.)
- 5) Remove DFC (digital firebox control box) from the floor of the unit.




6) Disconnect wire harness, ground wire and spark wire from DFC.



DFC

7) Connect the TPTH and TH wires - green to green and white to white as shown below.



8) Plug in receiver DC supply wire - as shown below.



9) Remove the hi/lo knob by removing 2 screws as shown below.



10) Install the stepper motor in the same location the hi/lo knob was removed from - with 2 screws as shown below.



11) Install 4 - AA batteries into the receiver.



12) Plug 'motor' wires into the back of the receiver and bundle wires with the wire clip - as shown below.






13) Reattach wires from step 5.




- 14) Reinstall the DFC box onto the velcro pad on the floor of the unit.
- **15)** Install the heat shield to the receiver with two screws and attach to the floor of the unit with a velcro pad.



Heat shield

16) From the wire harness, plug the FCM wire into the fan control module.



FCM wire

Fan Control Module


17) Install the heat shield onto the fan control module - then install onto the velcro pad located on the floor of the unit located left of the receiver.



- 18) Plug fan control module into recepticle located on the left hand side of the unit.
- 19) Match the remote control to the receiver see remote control instructions.
- 20) Reverse steps 2 and 1.
- 21) Check to ensure there are no gas leaks..

### **FLUSH LOUVERS**

- Install the top louver by sliding the two bracket clips into the brackets located underneath the top of the firebox.
- 2) Install the bottom louver by folding the louver down and then sliding the Bottom Louver bracket down onto the 2 pins on the base of the unit (Diagram1). Secure with 1 screw (Diagram 2).



3) Open the bottom louver. Pull the Burner ON/ OFF control box from inside the bottom of the fireplace and position the slots in the bracket over the 2 screws on the left side of the bottom louver. Push down to lock into place. Tighten the screws.



Screws on Burner ON/OFF control box



Burner ON/OFF control box attached to bottom flush louver.

### **DOUBLE SCREEN DOOR**

- 1) Pull out the top louver.
- Center the screen door and hook over the flush door.



 Open the screen door(s) and secure the screen door to the flush door front with 2 clips on the bottom left and right side.








Clip installed on right side.

### **OPTIONAL BAY DOOR**

The Bay louvers <u>MUST</u> be used with the Bay glass option.

The optional Bay door is an overlay on the flush front. The standard flush door and glass must remain on the unit.


- Hook the top of the bay door over the flush door flange and swing the bottom against the bottom flange of the flush door.
- Secure to the flush door bottom bracket with 2 screws provided.



Note: If any maintenance etc. must be done in the firebox, first remove the Bay louvers and door.


### **OPTIONAL BAY TRIM**

Attach the 4 supplied magnets, each to the back of the top and bottom trim pieces (space out evenly) and attach trim to the top and bottom of Bay door.




### **BAY LOUVERS**

1) Remove flush louver top heat shield by removing the 4 screws.




2) Install the bay louver top heat shield and secure with 4 screws.




Bay Louver Top Heat Shield

3) Install top louver by sliding the two bracket clips into the brackets located on top of the bay door. See below. The fitted louver leaves a small gap between faceplate bottom and louver top.



- 4) Install bottom louver by sliding the two bracket clips into the brackets located underneath the bay door. Secure with 1 screw into each Bottom Louver Mounting Bracket as per diagram below. Use the bottom hole in the bracket.
- Slide the valve extension knobs onto the valve knobs. Match the correct ext. knob with the valve knob.




6) Open the bottom louver. Pull the Burner ON/OFF control box from inside the bottom of the fireplace and position the slots in the bracket over the 2 screws on the left side of the bottom louver. Push down to lock into place. Tighten the screws.




Burner ON/OFF control box

### **FULL SCREEN DOORS**


- Before beginning the installation, remove the Glass Door from the unit. Refer to the manual for instructions.
- 2) Slide the Bottom Faceplate Bracket into the bottom of the unit, secure it into the pins located on the inside of the fire box. Once the bracket is in place, tighten the screws into the hinges on the left and right sides.






3) Before attaching the Full Screen Door Frame, remove the Screen Doors from the Full Screen Door Frame by fully opening the doors and lifting up off of the hinges. See important note in step 10.

- 4) a) Before attaching the Full Screen Door Frame to the unit, loosen the left and right side #8 Self Tapping Philips screws located on the inside top of the outer frame of the appliance. Also remove the center screw.
  - b) Slide the cut-outs in the Top and Bottom Flange of the Full Screen Door Frame under the screw heads which were loosened in step 4a). Once the Frame is in place, tighten the screws to secure. Also re-secure the top center screw through the oblong hole.






**NOTE:** Should the finished wall protrude beyond the face of the unit, you can accommodate up to 1/2" depth.


Simply push in the Full Screen Door Frame until it aligns against the finished wall. Secure Top Flange of Full Screen Door Frame as described in step 4 b).

For the Bottom Flange of the Full Screen Door Frame, push the bottom of the Frame until it aligns with the wall. Use the inner cut-outs to secure the base of the Frame using the 2 x #8 Self Tapping Phillips screws provided.


5) Install the Hinges to the Hinge Brackets on the left and right side of the Bottom Faceplate Bracket (seen in step 2), secure using 2 x #8 Self Tapping Philips screws per hinge.




6) Place the Bottom Frame near the hinges, and flip down the hinges from the Bottom Face Plate. Secure the hinges in place to the Bottom Frame, using 2x #8 Self Tapping Phillips screws per hinge.



7) Mount the Burner ON/OFF Control Box to the left side of the Bottom Grill using 2 x #8 - 1/4" Philips Head Screws.




- 8) Re-install Glass Door. Refer to the manual for instructions.
- 9) Slide the Top Grill into the louver brackets located on the inside top of the firebox. Push in place.



10) Install the Left and Right Side Screen Doors in the fully open position by placing over top of the hinges on the Full Screen Door Frame.

**NOTE:** Failure to install the doors in the fully open position could result in paint damage to the surface of the door.



11) Close screen doors.

# CONTEMPORARY FACEPLATE INSTALLATION PART 1 (DERATING TO LOWER BTU RATING)

# THIS CONVERSION MUST BE DONE BY A QUALIFIED GAS FITTER IF IN DOUBT DO NOT DO THIS CONVERSION!!

1) Shut off the gas supply.

2) a) Open the flush door and remove the door (see p.37 in the P33-4 manual).

b) Remove the logs, embers, and brick panels (if used).

Remove the 2 screws holding the Burner Assembly to the firebox base.
 Push the Burner Assembly to the left and lift out.

Contemporary Faceplate Derating Kit Contains:

**Qty. Part #**Description

1 904-434 Burner Orifice #


904-434 Burner Orifice #47 (Natural Gas) 904-241 Burner Orifice #56 (Propane Gas)

(NOTE: Must also use Kit #434-969 with

P33 units and Kit #425-972 with P33E units)


918-777 Decal Overlay

1 918-767 Instruction Sheet



Remove the 2 screws, push Burner Assembly to the left and lift out.

3) Remove burner orifice with a 1/2" wrench and discard. Use another wrench to hold on to the elbow behind the orifice.



Burner Orifice

4) Reinstall new burner orifice and tighten.

NG #47

\*LP #56 (LP Conversion - Must also use Kit #434-969 with P33 units and Kit #425-972 with P33E units)

5) Reverse Steps 1 and 2.

Note: Place Decal Derating P33-4 (918-777) to decal plate by overlaying existing decal located on the front side base of the unit.

\* For conversion from NG to LP refer to the NG to LP conversion section in the P33-4 manual.

### **CONTEMPORARY FACEPLATE INSTALLATION PART 2**

# CONTROL MOUNTING PLATE INSTALLATION

(FOR P33-4 UNIT WITH FACEPLATE ONLY)

- 1) Remove top and bottom louvers.
- 2) Remove ON/OFF switch (for P33-4) from the bottom louver.
- Attach ON/OFF switch to control mounting plate with one screw as shown below.



- 4) If installing the optional fan, see instructions below otherwise proceed with the installation of the control mounting plate.
- Install the control mounting plate over the pin, located at the left base of the unit. Secure with 1 screw as shown.



Pin


## **INSTALLING THE OPTIONAL FAN**

(FOR P33-4 UNIT WITH FACEPLATE ONLY)

120 Volt AC power is needed for the fan switch and blower. The fan can be hard wired if desired. The receptacle box should be installed on the left hand side of the unit by a qualified electrician. The neutral (wider) slot of the polarized receptacle should be at the top.


Unit must be grounded at all times. Do not cut the ground terminal off under any circumstances.

- 1) Shut the power off.
- 2) Turn the fan base on its side (with the base facing towards you) and then slide the fan in towards the rear of the unit. Turn the fan upright and slip it over the two mounting studs. Take care not to damage the insulation on the fan base. Ensure that the fan blades do not rub against the valve tubing. Diagram 1.
- 3) Connect fan ground cable to ground lug. Refer to wiring diagram.



ar receptacle. Diagram 1

5) Slide the thermodisc/cover assembly into the bracket clip on the underside of the firebox. Check that no wire will touch the hot surfaces. Diagram 2.



- 9) Secure the fan wires and power cord by attaching one of the adhesive backed wire holder clips (Part #910-199) onto the Fireplace base. Use the second clip to bundle up the wires approximately 4" from the control box. Ensure that there is no interference with the wires when the faceplate and trim are installed and that no wire will touch the hot metal surfaces or sharp edges.
- 10) Plug the fan power cord into the rear end of the receptacle box to provide the maximum clearance.
- 11) Clip the fan control box to the ON/OFF switch (already installed on the control mounting plate. Secure the fan control box with one screw as shown below.
- 12) Install control mounting plate to unit (see step 5 this page).





### TO REMOVE THE FAN

- 1) Shut the power off.
- 2) Reverse the above instructions.

Note: The bearings are lubricated for life. Do not lubricate them. Make sure you vacuum the fan area on a regular basis.

### IMPORTANT:

These fans collect a lot of dust from within your home. Ensure you maintain these fan motors on a regular basis by vacuuming out the fan blades and housing using a soft brush nozzle.

### **CONTEMPORARY FACEPLATE INSTALLATION PART 3**

Faceplate				
434-033	Mounting Plate			
434-514 Faceplate Support				
434-032 Control Shield				
434-018F	Heat Deflector			
434-516	Faceplate - Black			
434-516BL	Faceplate - Blue			
434-516R	Faceplate - Red			
434-517	Faceplate - Stainless Steel			

1) Install the control shield with 2 #8 - 1/2" Phillips screws to the bottom of the flush door as shown in Diagram 1.






Diagram 1

Install the heat deflector on the fire box as shown in Diagrams 2 & 3.
 Loosen 3 Phillips head screws already in firebox, slide heat deflector on to screws and retighten.






3) Loosen 4 phillips head screws located inside firebox, for screw locations see Diagram 4. Install mounting frame and retighten screws.




Diagram 4

4) After the frame has been installed, locate the 2 phillips head screws on lower part of the mounting frame- see Diagram 3 for location. Slide on the 2 faceplate supports and retighten the screws.

**Important:** Position of bracket must be as shown in Diagram 5, with bend away from fireplace.



5) The top of the faceplate has a flange that hooks over the top of the flush door.



6) Hook the flange on the faceplate over the top of the flush door and gently lower the faceplate into place until it rests against the faceplate supports as shown in Diagrams 7 & 8.




Diagram 7








Image of P33-4 with Faceplate

Diagram 9

Image of P33S with Faceplate

# Optional WALL THERMOSTAT

A wall thermostat may be installed if desired, connect the wires as per the wiring diagram. Use table below to determine the maximum wire length.

Note: Preferable if the thermostat is installed on an interior wall.

Regency® offers an optional programmable thermostat but any 250-750 millivolt rated non-anticipator type thermostat that is CSA, ULC or UL approved may be used.

CAUTION

Do not wire millivolt wall thermostat wires to 120V wire.

#### **Thermostat Wire Table**

Recommended Maximum Lead Length (Two-Wire) When Using Wall Thermostat (CP-2 System)			
Wire Size	Max. Length		
14 GA.	50 Ft.		
16 GA.	32 Ft.		
18 GA.	20 Ft.		
20 GA.	12 Ft.		
22 GA.	9 Ft.		

# Optional REMOTE CONTROL

Use the Regency® Remote Control Kit approved for this unit. Use of other systems may void your warranty.

The remote control kit comes with a hand held transmitter, a receiver and a wall mounting plate.

- Choose a convenient location on the wall to install the receiver and the receptacle box (protection from extreme heat is very important). Run wires from the fireplace to that location.
- 2) Connect the two wires to the gas valve. See wiring diagram. Optional wall switch GT/GTM/ GTMF using wire 0.584.907

# CAUTION Do not wire millivolt remote control wires to 120V wire.

3) Install 3AAA alkaline batteries in transmitter and 4 AA alkaline batteries in the receiver. Install the receiver and its cover in the wall. Switch the remote receiver to "remote" mode. The remote control is now ready for operation.

# Optional WALL SWITCH

 Run the supplied 10' of wire through the right or left side gas inlet opening. Be careful not to damage wire.

Note: We recommend a maximum of 10' of wire but if you wish to go with a longer run, use the Thermostat Wire Table.

Connect the wire to a wall switch and install into the receptacle box. Also attach wires to the valve as shown below.

CAUTION
Do not wire millivolt
wall switch wires
to 120V wire.

### **BATTERY INSTALLATION**

- 1) 4 AA batteries must be installed in the battery pack to operate the burner switch.
- 2) Install 2 AA batteries per side and connect as shown below.








### WIRING DIAGRAMS


This heater does not require a 120V A.C. supply for operation. In case of a power failure, the burner switch and the optional remote control/thermostat will continue to operate. However, a 120V A.C. power supply is needed for the fan/blower operation.

(Do not cut the ground terminal off under any circumstances.)

NOTE: Even if the fan is not purchased with the unit, it is still a good idea to bring power to the receptacle box (provided with the unit) in case the fan is installed at a later date.



**IMPORTANT:** If the optional remote control is used, the AA batteries normally installed into the battery holder must be removed. The AA batteries in the receiver now operate the unit. Having AA batteries in both the battery holder and receiver will damage the gas valve.



### INSTALLING THE OPTIONAL FAN

120 Volt AC power is needed for the fan switch and blower. The fan can be hard wired if desired. The receptacle box should be installed on the left hand side of the unit by a qualified electrician. The neutral (wider) slot of the polarized receptacle should be at the top.

Unit must be grounded at all times. Do not cut the ground terminal off under any circumstances.

- 1) Shut the power off.
- Remove the standard flush door and the optional bay door, if installed. Open the bottom louver door.
- Loosen the 2 screws holding the Burner ON/OFF switch and bracket to the bottom louver and lift the assembly out.



- 4) Turn the fan base on its side (with the base facing towards you) and then slide the fan in towards the rear of the unit. Turn the fan upright and slip it over the two mounting studs. Take care not to damage the insulation on the fan base. Ensure that the fan blades do not rub against the valve tubing. Diagram 1.
- 5) Connect fan ground cable to ground lug. Refer to wiring diagram.
- 6) Slide the thermodisc/cover assembly into the bracket clip on the underside of the firebox. Check that no wire will touch the hot surfaces. Diagram 2.
- Attach the Fan control box to the Burner ON/OFF control box. Diagram 3.




Diagram 1




Diagram 2



Diagram 3: Use the clip & hook on the side of the control boxes to join them together.

Secure the two boxes together with one screw.



Secure the 2 boxes together with one screw.

 Position the control box assembly on the bottom louver and mark the position of the slot on the right side bracket.



Hold control box assembly in place and mark the position of the right side slot

10) Remove the control box assembly and push the hold-down clip onto the louver. Bend the tab until it is at 90° to the louver.



Push hold-down clip onto inside louver and press tab until it is at 90° to louver.



11) Attach the two control boxes to the bottom louver and tighten the 2 screws on the left side and 1 screw on the right side.



Secure left side with 2 screws.



Secure right side with one screw.

- 12) Secure the fan wires and power cord by attaching one of the adhesive backed wire holder clips (Part #910-199) onto the Fireplace base. Use the second clip to bundle up the wires approximately 4" from the control box. Ensure that there is no interference with the wires when the louver is closed and that no wire will touch the hot metal surfaces or sharp edges.
- 13) Plug the fan power cord into the rear end of the receptacle box to provide the maximum clearance from the louvers.

#### TO REMOVE THE FAN

- 1) Shut the power off.
- 2) Reverse the above instructions.

Note: The bearings are lubricated for life.

Do not lubricate them. Make sure you vacuum the fan area on a regular basis.

### **IMPORTANT:**

These fans collect a lot of dust from within your home. Ensure you maintain these fan motors on a regular basis by vacuuming out the fan blades and housing using a soft brush nozzle.

### COPY OF THE LIGHTING PLATE INSTRUCTIONS

#### FOR YOUR SAFETY READ BEFORE LIGHTING

This appliance must be installed in accordance with local codes, if any; if none, follow the National Fuel Gas Code, ANSI Z223.1/NFPA 54, or Natural Gas and Propane Installation Codes, CSA B149.1.

WARNING: If you do not follow these instructions exactly, a fire or explosion may result causing property damage, personal injury or loss of life. Improper installation, adjustment, alteration, service or maintenance can cause injury or property damage. Refer to the owner's information manual provided with this appliance. For assistance or additional information consult a qualified installer, service agency or gas supplier. AVERTISSEMENT. Quiconque ne respecte pas à la lettre les instructions dans la présente notice

risquede déclencher un incendie ou une explosion entraînant des dommages, des blessures ou la mort.

Une installation, d'ajustement, de modification, de service ou d'entretien peut provoquer des blessures ou des dommages matériels. Reportez-vous au manuel du propriétaire de l'information fournie avec cet appareil. Pour obtenir de l'aide ou des informations supplémentaires consulter un installateur qualifié, une agence de service ou fournisseur de gaz.

- A) This appliance is equipped with an ignition device which automatically lights the pilot. Do not try to light the pilot by hand.
- B) BEFORE OPERATING smell all around the appliance area for gas. Be sure to smell next to the floor because some gas is heavier than air and will settle on the floor.

#### WHAT TO DO IF YOU SMELL GAS

- Do not try to light any appliance.
- Do not touch any electric switch, do not use any phone in your building.
- Immediately call your gas supplier from a neighbours phone. Follow the gas supplier's instructions.
- If you cannot reach your gas supplier, call the fire department.
- C) Do not use this appliance if any part has been under water. Immediately call a qualified service technician to inspect the appliance and replace any part of the control system and any gas control which has been underwater.
- A) Cet appareil est muni d'un dispositif d'allumage qui allume automatiquement la veilleuse. Ne tentez pas d'allumer la veilleuse manuellement.
- B) AVANT DE FAIRE FONCTIONNER, reniflez tout autour de l'appareil pour déceler une odeur de gaz. Reniflez près du plancher, car certains gaz sont pluslourds que l'air et peuvent s'accumuler au niveau du sol.
  - QUE FAIRE SI VOUS SENTEZ UNE ODEUR DE GAZ :
  - Ne pas tenter d'allumer d'appareil
  - Ne touchez à aucun interrupteur; ne pas vous servir des téléphones se trouvant dans le hâtiment
  - Appelez immédiatement votre fournisseur de gaz depuis un voisin. Suivez les instructions du fournisseur
  - Si vous ne pouvez rejoindre le fournisseur, appelez le service des incendies
- C) N'utilisez pas cet appareil s'il a été plongé dansl'eau, même partiellement. Faites inspecter l'appareil par un technicien qualifié et remplacez toute partie du système de contrôle et toute commande qui ont été plongés dans l'eau

CAUTION: Hot while in operation. Do not touch. Severe Burns may result. Due to high surface temperatures keep children, clothing and furniture, gasoline and other liquids having flammable vapors away. Keep burner and control compartment clean. See installation and operating instructions accompanying appliance

#### LIGHTING INSTRUCTIONS

- Turn on ON/OFF switch
   After approximately 4 seconds the spark ignition system will spark for 60 seconds to light the main burner.

Note: The first attempt to ignition will last approximately 60 seconds. If there is no flame ignition (rectifica-tion) the board will stop sparking for approximately 35 seconds. After this wait time, the board will start a second try for ignition by sparking for approximately 60 seconds. If there is still no positive ignition after the second attempt the board will go into lock out.

- The system will need to be reset as follows (after going into lock out mode):

  a) Wait 5 minutes turn the system off using ON/OFF switch.

  b) After approximately 2 seconds turn on ON/OFF switch or press ON/OFF button if using optional remote
  - c) Unit will repeat step 2
- 1) Appuyez le bouton ON / OFF
- 2) Attendre 4 secondes. Le système d'allumage produira des étincelles pendant 60 secondes afin d'amorcer le brûleur principal.
- 3) Les flammes s'allumeront.

Remarque: Au premier allumage, le système tente d'allumer les flammes pendant 60 secondes. Si l'essai est infructueux, le système fait une pause de 35 secondes. C'est ce qu'on appelle l'étape de rectification. Ce délai écoulé, le système tente à nouveau d'allumer les flammes en produisant des étincelles pendant 60 secondes. Si les flammes ne s'allument toujours pas, le système se met en mode verrouillage.

- Il faut alors le réinitialiser en suivant les étapes ci-dessous (pour le déverrouiller) :
  a) Attendre 5 minutes et éteindre l'appareil en réglant l'interrupteur à la position « OFF »;
- Attendre 2 secondes et rallumer le système à l'aide de l'interrupteur ou de la télécommande.
- c) L'unité répétera l'étape 2.

#### TO TURN OFF GAS APPLIANCE

- Turn off ON/OFF switch
- If service is to be performed you must disconnect power to the unit, from the battery pack, refer to
- Appuyez sur le bouton ON / OFF
- Si le service est effectuée, vous devez débrancher l'appareil, du bloc-piles, voir le manuel d'instruction pour plus de détails.

#### DO NOT REMOVE THIS INSTRUCTION PLATE

918-628b

# OPERATING INSTRUCTIONS

- 1) Read and understand these instructions before operating this appliance.
- 2) Check to see that all wiring is correct and enclosed to prevent possible shock.
- 3) Check to ensure there are no gas leaks.
- 4) Make sure the glass in the door frame is properly positioned. Never operate the appliance with the glass removed.
- 5) Verify that the venting and cap are unobstructed.
- 6) Ensure that the brick panels are installed.
- Verify log placement. If the pilot cannot be seen when lighting the unit, the logs have been incorrectly positioned.
- 8) The unit should never be turned off, and on again without a minimum of a 60 second wait.

### **FIRST FIRE**

The first fire in your fireplace is part of the paint curing process. To ensure that the paint is properly cured, it is recommended that you burn your fireplace for at least four (4) hours the first time you use it with the fan on.

When first operated, the unit will release an odour caused by the curing of the paint, the burning off of any oils remaining from manufacturing. Smoke detectors in the house may go off at this time. Open a few windows to ventilate the room for a couple of hours.

The glass panel may require cleaning after the unit has cooled down. DO NOT ATTEMPT TO CLEAN THE GLASS WHILE IT IS HOT.

Note: When the glass is cold and the appliance is lit, it may cause condensation and fog the glass. This condensation is normal and will disappear in a few minutes as the glass heats up.

# DO NOT BURN THE APPLIANCE WITHOUT THE GLASS FRONT IN PLACE.

During the first few fires, a white film may develop on the glass front as part of the curing process. The glass should be cleaned or the film will bake on and become very difficult to remove. Use a non-abrasive cleaner and NEVER clean the glass while it is hot.

# LIGHTING PROCEDURE

# IMPORTANT To ignite or reignite the pilot, you must first remove the glass door.

- Press and release on ON/OFF button once on the remote control or ON/OFF switch.
- After approximately 4 seconds the spark ignition system will spark for 60 seconds to light the main burner.
- 3) The unit will turn on.

Note: The first try for ignition will last approximately 60 seconds. If there is no flame ignition (rectification) the board will stop sparking for approximately 35 seconds. After wait time, the board will start second try for ignition by sparking for approximately 60 seconds. If there is still no positive ignition the board will go into lock out.

The system will need to be reset as follows:

- a) Turn the system off using ON/OFF switch or press ON/OFF button - if using optional remote.
- b) After approximately 2 seconds turn on ON/ OFF switch or press ON/OFF button if using optional remote.
- c) Repeat step 2.

# SHUTDOWN PROCEDURE

- Turn the wall mounted switch or remote to the "OFF" position.
- 2) Press "OFF" on the remote control.
- Turn the gas control knob to the "OFF" position to turn off the pilot.

# AERATION ADJUSTMENT


The air shutter can be adjusted by moving the adjusting wire up or down. The wire is accessed through the bottom louver opening. Open the air shutter for a blue flame or close for a yellower flame. The burner aeration is factory set but may need adjusting due to either the local gas supply or altitude.

Minimum Air Shutter Opening: 3/16" Natural Gas - Orifice # 44 1/8" NG (w/faceplate) - Orifice #4

1/8" NG (w/faceplate) -Orifice #47
3/8" Propane - Orifice # 54

1/4" LP (w/faceplate) - Orifice #56

**CAUTION:** Carbon will be produced if air shutter is closed too much.



Adjustment Wire: push to close or pull to open aeration cap

Closed - Tall yellow Open - Short blue

Note: Any damage due to carboning resulting from improperly setting the aeration controls is NOT covered under warranty.

Note: Aeration Adjustment should only be performed by an authorized Regency® Installer at the time of installation or service.

# NORMAL OPERATING SOUNDS OF GAS APPLIANCES

It is possible that you will hear some sounds from your gas appliance. This is perfectly normal due to the fact that there are various gauges and types of steel used within your appliance. Listed below are some examples. All are **normal operating sounds** and should not be considered as defects in your appliance.

#### Blower:

Regency® gas appliances use high tech blowers to push heated air farther into the room. It is not unusual for the fan to make a "whirring" sound when ON. This sound will increase or decrease in volume depending on the speed setting of your fan speed control.

#### **Burner Tray:**

The burner tray is positioned directly under the burner tube(s) and logs and is made of a different gauge material from the rest of the firebox and body. Therefore, the varying thicknesses of steel will expand and contract at slightly different rates which can cause "ticking" and "cracking" sounds. You should also be aware that as there are temperature changes within the unit these sounds will likely re-occur. Again, this is normal for steel fireboxes.

#### **Blower Thermodisc:**

When this thermally activated switch turns ON it will create a small "clicking" sound. This is the switch contacts closing and is normal.

### Pilot Flame:

While the pilot flame is on it can make a very slight "whisper" sound.

#### **Gas Control Valve:**

As the gas control valve turns ON and OFF, a dull clicking sound may be audible, this is normal operation of a gas regulator or valve.

#### Unit Body/Firebox:

Different types and thicknesses of steel will expand and contract at different rates resulting in some "cracking" and "ticking" sounds will be heard throughout the cycling process.

# MAINTENANCE INSTRUCTIONS

- Always turn off the gas valve before cleaning.
   For relighting, refer to lighting instructions.
   Keep the burner and control compartment clean by brushing and vacuuming at least once a year. When cleaning the logs, use a soft clean paint brush as the logs are fragile and easily damaged.
- 2) Clean appliance and door with a damp cloth (never when unit is hot). Never use an abrasive cleaner. The glass should be cleaned with a gas fireplace glass cleaner. The glass should be cleaned when it starts looking cloudy.
- The heater is finished in a heat resistant paint and should only be refinished with heat resistant paint. Regency<sup>®</sup> uses StoveBright Paint - Metallic Black #6309.
- 4) Make a periodic check of burner for proper position and condition. Visually check the flame of the burner periodically, making sure the flames are steady; not lifting or floating. If there is a problem, call a qualified service person.
- 5) The appliance and venting system must be inspected before use, and at least annually, by a qualified field service person, to ensure that the flow of combustion and ventilation air is not obstructed.

Note: Never operate the appliance without the glass properly secured in place.

- 6) Do not use this appliance if any part has been under water. Immediately call a qualified service technician to inspect the appliance and to replace nay part of the control system and any gas control which has been under water.
- 7) Verify operation after servicing.

# GENERAL VENT MAINTENANCE

Conduct an inspection of the venting system semi-annually. Recommended areas to inspect as follows:

- Check the Venting System for corrosion in areas that are exposed to the elements. These will appear as rust spots or streaks, and in extreme cases, holes. These components should be replaced immediately.
- Remove the Cap, and shine a flashlight down the Vent. Remove any bird nests, or other foreign material.
- 3) Check for evidences of excessive condensation, such as water droplets forming in the inner liner, and subsequently dripping out the joints, Continuous condensation can cause corrosion of caps, pipe, and fittings. It may be caused by having excessive lateral runs, too many elbows, and exterior portions of the system being exposed to cold weather.
- 4) Inspect joints, to verify that no pipe sections or fittings have been disturbed, and consequently loosened. Also check mechanical supports such as Wall Straps, or plumbers' tape for rigidity.

# GOLD-PLATED LOUVERS/TRIM

The 24 carat gold-plated finish on the louvers and trim requires little maintenance, and need only be cleaned with a damp cloth. DO NOT use abrasive materials or chemical cleaners, as they may harm the finish and void the warranty. Clean any fingerprints off before turning the unit on.

### LOG REPLACEMENT

The unit should never be used with broken logs. Turn off the gas valve and allow the unit to cool before opening door and carefully remove the logs. (The pilot light generates enough heat to burn someone.) If for any reason a log should need replacement, you must use the proper replacement log. The position of these logs must be as shown in the diagrams under Log Installation.

Note: Improper positioning of logs may create carbon build-up and will severely alter the unit's performance which is not covered under warranty.

### **GLASS GASKET**

If the glass gasket requires replacement use 5/8" flat glass gasket for the Bay Front (Part # 936-243) and a tadpole glass gasket for the Flush Front (Part # 936-155).

### **DOOR GLASS**

Your Regency® fireplace is supplied with high temperature, 5 mm Neoceram ceramic glass that will withstand the highest heat that your unit will produce. If your glass requires cleaning, we recommend using an approved glass cleaner available at all authorized dealers. Do not use abrasive materials. Do not clean the glass when hot.

In the event that you break your glass by impact, purchase your replacement from an authorized Regency® dealer only, and follow our step-bystep instructions for replacement.


WARNING: Do not operate the appliance with the glass panels removed, cracked or broken. Replacement of the glass panels should be done by a licensed or qualified service person.



Caution: Wear gloves when removing damaged or broken glass.


### Flush Glass Replacement

Remove the flush door front. Remove the 4 glass clips from each corner. Slide in the new replacement glass. Push the 4 glass clips back onto the frame. The glass must have gasketing around it.



### **Bay Glass Replacement**

- 1) Remove the door from the unit and place on a soft surface to prevent scratching.
- 2) Remove the nuts holding the glass clips in place and remove.
- 3) Replace the glass. The glass must have gasketing around it.
- 5) Reverse the previous steps, replace the glass clips and fasten with the nuts but do not over tighten, as this can break the glass.
- **6)** Replace door on the Fireplace and check the seal.



### **REMOVING VALVE**


- 1) Shut off the gas supply.
- 2) Remove the louvers (and bay door if installed.)
- 3) Open the flush door and remove the door.
- 4) Remove the logs.
- 5) Remove the burner/grate assembly by removing the two screws and then lift the burner assembly out.





Diagram 1: Remove the left and right screws and then lift out the burner/grate assembly.

- 6) Remove the rear log stand by removing the 2 screws.
- 7) Disconnect the inlet gas line.
- 8) Disconnect the EV1, EV2, and ground wires from the valve as shown below.



9) Remove the 10 screws securing the valve tray assembly in place (diagram 2) and then lift the entire assembly out (diagram 3).




Diagram 2: Rear Log Stand & Valve Tray Assembly

10) Remove valve tray assembly.





Diagram 3: Lift out Valve Tray Assembly

### **INSTALLING VALVE**

- 1) Install new valve assembly.
- 2) Reverse steps 9-1.

# **MAIN ASSEMBLY**


Part #	Description	Part #	Description		Part #	Description
1) 948-247	Door Handle	432-901	Brick Panel Set - Standard Brown		946-556	Optional Heat Wave Duct Kit
2) *	Thermodisc Bracket	432-902	Brick Panel Set - Standard Red	89)	946-004	Junction Box
		432-903	Brick Panel Set - Herringbone	90)	946-000	Round Duct Adaptor
7) 910-428	Duplex Receptacle		Brown	91)	946-002	Round to Oval Adaptor
8) 910-429	Box - Receptacle			92)	946-001	Oval Duct Adaptor
9) 910-430	Cover - Receptacle	33) *	Brick Panel - Rear	93)	946-007	Angle Bracket
10) 904-687	Clamp Connector	34) *	Brick Panel - Left Side	94)	946-517/F	PFan Assembly - HeatWave
13) 948-045	#12 Jack Chain	35) *	Brick Panel - Right Side			Option
14) 948-115	Door Extension Spring	36) *	Brick Panel - Top	95)	946-006	Grill Plate - White
		37) 430-056	Brick Clip - Top	96)	946-005	Wall Adaptor Plate - White
16) *	Thermodisc Top	38) 430-057	Brick Clip - Bottom	97)	910-417	Knob - White
17) *	Thermodisc Box Base			98)	910-366	Switch Cover Plate - White
19) 430-129	Receptacle Box Mount	432-917	Fan Assembly (120 Volts)	99)	910-412	Fan Speed Controller
			Optional	100)	910-367	Box - Plastic Switch
20) 430-031	Top Nailing Strip	42) 910-331/P	Fan Motor (120 Volts)			Receptacle
21) 430-032	Side Nailing Strip	432-966	Fan Switch Assy (120 Volts)	102)	946-010	Flexible Air Duct
22) 433-017	Firebox Baffle	43) 910-813	Power Cord (120 Volts)		946-038	Insulation 6" dia. x 24"
23) 433-011F	Top Standoff	46) 910-330	Fan Speed Control	104)	690-022F	Cover Plate
24) 511-044	Standoff - Side	47) 904-586	Knob - Speed Control			
26) *	Louver Hold Down	49) 910-142	Thermodisc - Fan Auto		510-994	Rigid Pipe Adaptor
27) *	Outer Flue Collar		ON/OFF		918-849	Manual
28) *	Inner Flue Collar Assembly	50) 904-713	U-Clip at Louver		425-972	Conversion Kit - NG to LP
30) *	Gasket - Flue Collar	432-967	Burner On/Off Switch Assy			
31) *	Flue Mounting Plate	63) 910-241	Switch - Burner On/Off	*No	available	as a replacement part.
		910-899	Wire Harness - Valve to Burner			



# **BURNER & LOG ASSEMBLY**

Part	Description
53) 430-055 54) 910-421 55) 910-422	Gasket - Valve Access Plate - NG/LP Pilot ON/OFF Extension Knob Flame HI/LOW Extension Knob
433-574E/F 433-576E/F 57) 911-004 911-005	
58) * 59) * 60) * 66) 911-006 911-007 904-568 904-163 936-170 67) * 68) W840470 79) 433-525 82) 433-024 83) * 85) 431-930 86) 430-097 87) 433-018	Valve Bracket Firebox Base Valve Tray Pilot Assy - 886 - S.I.T NG Pilot Assy - 886 - S.I.T LP Orifice #44 - Natural Gas Orifice #54 - Propane Orifice Gasket Pilot Holder Pilot Assembly Gasket Burner Assy - NG/LP Burner Grate Assembly - NG/LP Rear Log Support Bracket - NG/LP Log Set Air Deflector-Left Air Deflector-Right


<sup>\*</sup>Not available as a replacement part.



# **FLUSH FRONT & LOUVERS**


	Part #	Description		Part #	Description
117)	904-196	Magnet - 1' round		430-940	Finishing Trim (Set) - Black (Option)
131)	430-947	Flush Glass Trim (set) - Brushed Steel (Option)	157)	*	Finishing Trim Left
			159)		Finishing Trim Right
	430-918	Flush Louvers (set) - Gold/Black (Option)	158)	*	Finishing Trim Top
	430-922	Flush Louvers (set) - Black (Option)			
	430-923	Flush Louvers (set) - Black/Steel (Option)		431-943	Double Screen Door Complete (Option)
133)	*	Flush Louver Assy-Top	171)	*	Door Frame Left Assembly
	430-162	Front Deflector	172)	*	Door Frame Right Assembly
134)	*	Flush Louver Assy-Bottom	173)	904-712	U-Clip for Frame
			174)	430-133	Door Handle
	433-538	Flush Door Assembly Complete	175)	511-084	Door Latch
135)	940-088/P	Glass (Flush)	178)	*	Door Support Frame Assembly
137)	904-691	U-Clip	,	904-715	Pushnut Fastener 3/16"
139)	936-155	Glass Gasket (Tadpole)		*	Screw - #8 x 1/2"
140)	948-042	Spring Hinge - Black			
,			179)	948-216	Regency® Logo Plate

<sup>\*</sup>Not available as a replacement part.




# **CONTEMPORARY FACEPLATE**

	Part #	Description
1)	434-516 434-516BL 434-516R 434-517	Faceplate Assembly Black Faceplate Assembly Painted Blue Faceplate Assembly Painted Red Faceplate Assembly Stainless Steel
2)	434-033	Mounting Plate
3)	434-514 909-924 904-925	Faceplate Support Bracket Assembly Bumper Rubber W/Machine Screw 8-32 x 3/8" Cap Assy Brushed Stainless 3/4" diameter.
4)	434-032	Control Shield
5)	434-018F	Heat Deflector
6)	904-434 904-241	Burner Orifice #47 (Natural Gas) Burner Orifice #56 (Propane Gas)



OTES			
OIL3			
-	-		



OTES			
OIL3			
-	-		



Regency Fireplace Products are designed with reliability and simplicity in mind. In addition, our internal Quality Assurance Team carefully inspects each unit thoroughly before it leaves our facility. FPI Fireplace Products International Ltd. is pleased to extend this limited lifetime warranty to the <u>original purchaser</u> of a Excalibur Product. This warranty is not transferable.

#### The Warranty: Limited Lifetime

The combustion chamber, heat exchanger, burner tubes/pans, logs, brick panels and gold plating (against defective manufacture only) are covered under the Limited Lifetime Warranty for five (5) years for parts and subsidized labour\* and parts only thereafter.

Glass is covered for lifetime against thermal breakage only, parts and subsidized labour\* for five (5) years and parts only thereafter from date of purchase.

External casting, surrounds and grills are covered against cracks and warps resulting from manufacturer defects, parts and subsidized labour\* for three (3) years from the date of purchase and parts only thereafter.

Special Finishes - One year on brushed nickel and antique copper full screens and doors. You can expect some changes in color as the product "ages" with constant heating and cooling. FPI warranties the product for any manufacturing defects on the original product. However, the manufacturers warranty does not cover changing colors and marks, ie. finger prints, etc applied after the purchase of the product. Damage from the use of abrasive cleaners is not covered by warranty.

Electrical and mechanical components such as blowers, switches, wiring, thermodiscs, FPI remote controls, spill switches, thermopiles, thermocouples, pilot assembly components, and gas valves are covered for two years parts and one year subsidized labour\* from the date of purchase. Blowers and valves replaced under warranty are considered repairs and continue as if new with appliance. ie. twelve (12) months from original purchase date of appliance with a minimum of three (3) months coverage from date of replacement.

FPI venting components are covered parts and subsidized labour\* for three (3) years from date of purchase.

Simpson Dura-Vent venting components (Direct Vent units) are covered by Simpson Dura-Vent Inc. warranty.

Repair/replacement parts purchased by the consumer from FPI after the original coverage has expired on the unit will carry a 90 day warranty, valid with a receipt only. Any item shown to be defective will be repaired or replaced at our discretion. No labor coverage is included with these parts.

#### Conditions

Any part or parts of this unit which in our judgement show evidence of such defects will be repaired or replaced at FPI's option, through an accredited distributor or agent provided that the defective part be returned to the distributor or agent <u>Transportation Prepaid</u>, if requested.

Porcelain/Enamel - Absolute perfection is either guaranteed nor commercially possible. Any chips must be reported and inspected by an authorized dealer within three days of installation. Reported damage after this time will be subject to rejection.

It is the general practice of FPI to charge for larger, higher priced replacement parts and issue credit once the replaced component has been returned to FPI and evaluated for manufacturer defect.

The authorized selling dealer is responsible for all in-field service work carried out on your Regency product. FPI will not be liable for results or costs of workmanship from unauthorized service persons or dealers.

At all times FPI reserves the right to inspect product in the field which is claimed to be defective.

All claims must be submitted to FPI by authorized selling dealers. It is essential that all submitted claims provide all of the necessary information including customer name, purchase date, serial #, type of unit, problem, and part or parts requested, without this information the warranty will be invalid.

#### Exclusions:

This limited Lifetime Warranty does not extend to or include paint, door or glass gasketing or trim.

At no time will FPI be liable for any consequential damages which exceed the purchase price of the unit. FPI has no obligation to enhance or modify any unit once manufactured. ie. as products evolve, field modifications or upgrades will not be performed.

FPI will not be liable for travel costs for service work.

Installation and environmental problems are not the responsibility of the manufacturer and therefore are not covered under the terms of this warranty policy.

Embers, rockwool, gaskets, door handles and paint are not covered under the terms of this warranty policy.

Any unit which shows signs of neglect or misuse is not covered under the terms of this warranty policy.

The warranty will not extend to any part which has been tampered with or altered in any way, or in our judgment has been subject to misuse, improper installation, negligence or accident, spillage or downdrafts caused by environmental or geographical conditions, inadequate ventilation, excessive offsets, negative air pressure caused by mechanical systems such as furnaces, fans, clothes dryer, etc.

Freight damage to stoves and replacement parts is not covered by warranty and is subject to a claim against the freight carrier by the dealer.


FPI will not be liable for acts of God, or acts of terrorism, which cause malfunction of the appliance.

Performance problems due to operator error will not be covered by this warranty policy.

Products made or provided by other manufacturers and used in conjunction with the operation of this appliance without prior authorization from FPI, may nullify your warranty on this product.

Any alteration to the unit which causes sooting or carboning that results in damage to the interior / exterior facia is not the responsibility of FPI.

\* Subsidy according to job scale as predetermined by FPI.



Register your Regency® online at http://www.regency-fire.com

ınstaller: Ple	ase complete the folio	owing information	
Dealer Name	& Address:		 
Installer:			
Date Installe	l:		
Serial No.:			